BEFORE THE BOARD OF OIL, GAS AND MINING DEPARTMENT OF NATURAL RESOURCES THE STATE OF UTAH

IN THE MATTER OF THE PETITION OF RAYMOND T. DUNCAN FOR APPROVAL OF A WATERFLOOD SECONDARY RECOVERY PROJECT AND SIMULTANEOUS HEARING OF A CLASS II INJECTION WELL APPLICATION, IN THE CAVE CANYON FIELD, SAN JUAN COUNTY, UTAH

FINDINGS OF FACT, CONCLUSIONS OF LAW, AND ORDER

Docket No. 89-005 Cause No. 217-1

This cause came on regularly for hearing before the Board of Oil, Gas & Mining (the "Board") on Thursday, March 23, 1989; April 27, 1989; and May 25, 1989, in the Board Room of the Division of Oil, Gas and Mining, 3 Triad Center, Suite 301, 355 West North Temple, Salt Lake City, Utah.

The following Board members were present at one or more of the hearings: Gregory P. Williams, Chairman; E. Steele McIntyre, Charles R. Henderson, Judy F. Lever, James M. Carter, Richard B. Larsen, and John M. Garr. Also present representing the Division were Dr. Dianne R. Nielson, Director; Ronald J. Firth, Associate Director Oil and Gas; John R. Baza, Petroleum Engineer; and Barbara W. Roberts, Assistant Attorney General and Counsel to the Division. Participating and representing the Bureau of Land Management (BLM) were Robert A. Henricks

(Chief, Branch of Fluid Minerals, Utah State Office) and Steve Jones (Petroleum Engineer, Moab District Office). Testifying on behalf of Petitioner Raymond T. Duncan were Steve Fallin, Production Manager; Robert Lentz, geologist; Daniel H. Stright, Jr., consulting petroleum engineer with Reservoir Management Services, Inc.; and John L. Moore, independent consulting professional landman. Duncan was represented by Robert G. Pruitt, Jr. of Pruitt, Gushee & Fletcher. Testifying for Respondent and Counter-Petitioner Yates Petroleum Corporation were Dr. David F. Boneau, Engineering Manager; and Steven W. Speer, staff geologist. Yates was represented by Phillip Wm. Lear of Van Cott, Bagley, Cornwall & McCarthy. No other parties appeared or participated in the hearing.

The Board appointed James M. Carter as the hearing examiner for purposes of taking evidence regarding the allocation formula. Mr. Carter conducted hearings on the allocation formula on April 27, 1989, and May 2, 1989, respectively. The same parties and witnesses appeared before the hearing examiner as before the Board.

NOW THEREFORE, The Board, having fully considered the testimony adduced and the exhibits received at the hearings and being fully advised in the premises, now makes and enters its Findings of Fact, Conclusions of Law and Order as follows:

FINDINGS OF FACT AND CONCLUSIONS OF LAW

- 1. In accordance with Petitioner's Motion for Expedited Hearing, to which Respondent has concurred, due and regular notice of the time, place, and purpose of the hearing was given to all interested parties in the form and manner and within sufficient time as required by law and the rules of the Board.
- 2. The Board has jurisdiction over the matters covered by said Petition and Counter-Petition, and over all parties interested therein, and has jurisdiction to make an promulgate the Order hereinafter set forth.
- 3. Raymond T. Duncan is an individual residing in Denver, Colorado. Mr. Duncan and his various oil and gas companies ("Duncan") own and operate federal leases and wells in the Cave Canyon Field Area.
- 4. Yates Petroleum Corporation ("Yates") owns and operates federal leases and wells in the Cave Canyon Field Area.
- 5. The Yates Cave Canyon Federal No. 1-33 Well located in the $SW_2^1SE_2^1$ of Section 33 is on the geologic structure proposed for waterflood operations and produces from the Upper Ismay formation.
- 6. The Yates Cave Canyon Federal No. 1-33 Well is within the same porosity system as the Duncan wells proposed for waterflooding, and the structure embraces one continuous reservoir requiring unitization.

7. The Unit boundaries for the proposed Cave Canyon Field Secondary Recovery Unit (the "Unit") area have been stipulated by the parties to embrace the following described lands in San Juan County, Utah:

Township 37 South, Range 24 East, S.L.M.

Section 33: SE\SW\\\4, S\\\2SE\\\4

Township 38 South, Range 24 East, S.L.M.

Section 3: W1, W2SE4

Section 4: NE\(\frac{1}{2}\), NE\(\frac{1}{2}\)NW\(\frac{1}{2}\), NE\(\frac{1}{2}\)SE\(\frac{1}{2}\),

(containing 760 acres, more or less)

8. The formation to be unitized for secondary recovery operations is the Upper Ismay Zone of the Paradox formation, more particularly described as follows:

The interval as identified in the gamma ray-density log run in the Cave Canyon Federal #3-1 Well located in the SW\(\frac{1}{2}\)NW\(\frac{1}{2}\) of Section 3, Township 38 South, Range 24 East, S.L.M., with the top being at a depth of 5,702 feet below the surface of the Kelly Bushing (-360 subsea) and the base being at a depth of 5,882 feet below the surface of the Kelly Bushing (-540 subsea).

- 9. The hydrocarbon pore volume map prepared by Duncan Exploration Company and offered in evidence as Yates Exhibit 1-B should be used for the purpose of allocating interest in the Unit.
- 10. The factors for allocating participation in the Unit should be (a) cumulative oil production to date and (b) hydrocarbon pore volume (HCPV), weighted 25%-75%, respectively. The share of Yates cumulative oil production to

date is 2.5%, while Yates' share of hydrocarbon pore volume is 2.56%. Therefore, the share of interest attributable to the Yates leasehold and well in the Unit is $(2.5\% \times 25\%) + (2.56\% \times 75\%)$ 2.545%. The remaining shares of interest, 97.455%, is attributed to th Duncan leasehold and wells.

- 11. The value of the estimated additional recovery of oil or gas substantially exceeds the additional costs incident to conducting secondary recovery operations.
- 12. Petitioner's proposed water injection and waterflood project for the Cave Canyon Field is necessary for the purposes of Chapter 6, Title 40, <u>Utah Code Annotated</u>.
- 13. No voluntary agreement of the type contemplated by section 40-6-7(1) of the <u>Utah Code Annotated</u>, and no plan of development and operation of the pool as a unit as contemplated by section 40-6-7(2) of the <u>Utah Code Annotated</u> exist with respect to secondary recovery operations within the proposed Cave Canyon Field Unit.
- 14. The secondary recovery will be achieved by water injection and waterflood programs.
- 15. The proposed Unit Agreement creates a working interest unit to be known as the "Cave Canyon Field Secondary Recovery Unit". The basic landowner's royalty is not unitized and will be paid on a leasehold basis. In all cases the working interest or operating rights in the subject lands and formations will be unitized for secondary recovery operations.

- 16. In excess of 70% of all owners of working interest (operating rights) are prepared to execute the Unit Agreement.
- 17. Duncan Exploration Company will be the unit operator for the Unit.
- 18. The Bureau of Land Management, Branch of Fluid Minerals, has approved the plan of development.
- 19. Secondary recovery operations contemplated by the Unit Agreement are in the public interest and promote conservation, will increase ultimate recovery, will prevent waste, and will protect the correlative rights of each owner or producer.
- 20. The proposed Unit Agreement introduced at the hearing as Exhibit "C," together with all attachments, contain all of the provisions required by statute and are acceptable to the Division as modified.
- 21. The plan of unit development contained in the Waterflood Feasibility Study of the Cave Canyon Field dated March 1, 1989 (the "Study Report"), introduced at the hearing as Exhibit "D" supports the contemplated secondary recovery by injection of water and waterflood procedures and is acceptable to the Division as submitted.
- 22. Petitioner's Class II UIC published petition received no protests and should be approved as proposed.

ORDER

After considering all testimony and evidence presented at the hearings, the findings of the hearing examiner, and the comments received from the staff of the Division and the BLM, the Board enters the following Order:

- 1. The waterflood project and plan of operation proposed by Petitioner, as described in the Study Report is hereby approved by the Board with the changes involving unitization and allocation of interests ordered herein as provided under sections 40-6-7 and 40-6-8 of the <u>Utah Code Annotated</u>.
- 2. Unitization sought by Counter-Petitioner is hereby granted, as modified by this Order.
- 3. The lands and formations described in paragraphs 7 and 8 of the Findings of Fact constitute a pool for the operation of a waterflood secondary recovery unit in the Upper Ismay Zone of the Paradox formation, and this Board hereby establishes the same as a pool to be operated as a unit for the continued operation of all wells thereon.
- 4. The unit hereby established shall be known as the "Cave Canyon Field Secondary Recovery Unit."
- 5. The Unit Agreement, together will all attachments, is hereby approved as modified.

- 6. The Unit Agreement shall be binding upon all owners of working interest or operating rights when the owners who are required to pay 70% of the costs of unit operation approve in writing and join in execution of the Unit Agreement and Unit Operating Agreement, as authorized by sections 40-6-7 and 40-6-8 of <u>Utah Code Annotated</u>. All such written approvals must be obtained within six (6) months from the effective date of this order, or this order shall become ineffective and shall be revoked by the Board unless, for good cause shown, the Board extends the time for approval
- 7. The interest of the owners of the overriding royalty or leasehold burdens other than the basic lessor's royalty shall be committed to the unit upon the joinder of any such owner's interest. The lessor's royalty shall be paid on a leasehold basis, and the interest of any other non-cost bearing owner shall be paid on a leasehold basis if the owner thereof does not voluntarily join the Unit. The lessor's royalty likewise may be committed to the unit upon the lessor's subsequent approval, without hearing and subsequent order of the Board.
- 8. Any owner of working interest/operating rights who does not voluntarily commit his interest to the Unit shall be a "non-consenting owner" and shall be deemed to have contracted with the unit operator for his proportionate part of the cost of developing and operating the Unit Area, in

accordance with section 40-6-8(3)(e) of the <u>Utah Code</u> Annotated.

- 9. The allocation formula described in paragraph 10 of the Findings of Fact, which is based upon cumulative oil production and hydrocarbon pore volume (HCPV), is hereby approved.
- 10. Spacing orders and/or state-wide field or well location and siting rules affecting the subject lands and formation are hereby suspended to the extent said orders or rules are inconsistent with the Unit Agreement for development of the Unit.
- 11. This order does not waive jurisdiction of the Board over the Underground Injection Control (UIC) Program with respect to the injection wells contemplated for the Cave Canyon Field Unit Area, and expressly directs Petitioner to comply with all requirements and procedures of the UIC Program.
- 12. The underground injection well program proposed by Petitioner in connection with said project is approved by the Board in accordance with applicable statutes and regulations.
- 13. The Board retains continuing jurisdiction over the subject matter and the parties for purposes of considering any amendments or revisions to the plans of operation, the Unit Agreement governing unit operations, and the lands affected by the unit.

Entered this 23-d day of June, 1989, but effective May 25, 1989.

> STATE OF UTAH BOARD OF OIL, GAS AND MINING


Gregory P Chairman

Approved as to form:

Robert G. Pruitt, Jr. Attorney for Petitioner

Phillip/Wm. Lear

Attorney for Respondent



(777 SOUTH HAPRISON STREET PENTHOUSE ONE TELEPHONE (303) 759-3303 DENVER COLDRADO ACE. C

June 5, 1990

Bureau of Land Management P. O. Box 970 Moab, UT 84532

> Re: Cave Canyon No. 3-5 2550' FEL & 2150' FSL NW SE Sec. 3-T38S-R24E San Juan County, UT

Gentlemen:

This letter is to inform you that Permitco is authorized to act as Agent and to sign documents on behalf of Raymond T. Duncan when necessary for filing County, State, and Federal permits including Onshore Order No. 1, Right-of-Way applications, etc., for the above captioned well.

It should be understood that Permitco is acting as Agent only in those matters stated above and is not responsible for drilling, completion, production, or compliance with regulations.

Raymond T. Duncan agrees to accept full responsibility for operations conducted in order to drill, complete, and produce the above captioned well.

Sincerely,

RAYMOND T. DUNCAN

W. S. Fallin

Production Manager

WSF:kb





Bureau of Land Management Moab District P.O. Box 970 Moab, UT 84532

Re: Duncan Energy Company

Cave Canyon Federal #3-5 NW SE Sec. 3, T38S - R24E San Juan County, Utah Lease No. U-47876

Gentlemen:

The above reference location was previously permitted by Raymond T. Duncan and approved by your office on July 16, 1992. The well was never drilled and the application was returned to Duncan on July 29, 1991.

Duncan Energy Company proposes to spud this well on approximately October 1, 1992 and therefore, we are resubmitting the required application.

If you should have any questions, or need additional information, please contact me at your earliest convenience.

Sincerely,

PERMITCO INC.

Lisa L. Smith Consultant for:

Duncan Energy Company

Less & Smila


Enc.

cc: Duncan Energy Company - Denver, CO Division of Oil, Gas & Mining - SLC, UT

Permitco Incorporated

A Petroleum Permitting Company

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING



5. Lease Designation and Serial No.

(Other instructions on reverse side)

15. No. of acres assigned to this well and to this well to this well and to this well and to this well and to this well and to the set of the proposed set on the sease of the proposed set on the sease. The proposed set of the sease of the		,	,			U-47876	
DRILL [XX] DEPPEN Depth Service PLUG BACK To service Servic	APPLICATION	FOR PERMIT TO	O DRILL, DEEPE	N, OR PLUG	BACK 6		or Tribe Name
Type of Well Well (DX Well Other State Other Oth							me
Single Charles of State of Operator Ope		. <u>[X]</u> X	DEEPEN .	PLUG BA	YCK 🔲 ,	-	
Well W. Well Other 303/759-3303 1777 S. Harrison St., PH-1 Duncan Energy Company Denver. CO 80210 Denver. CO 80210 See 37. September 203/452-8888 13585 Jackson 1 2 2 150' FSL and 2550' FEL AUG 2 7 1992 Eastern of Well Televor location clearly and in accordinate with any State requirement of the surface 2 150' FSL and 2550' FEL AUG 2 7 1992 Eastern of Well Televor location clearly and in accordinate with any State requirement of the surface 2 150' FSL and 2550' FEL AUG 2 7 1992 Eastern of Well Televor location clearly and in accordinate with any State requirement of the surface 2 150' FSL and 2550' FEL AUG 2 7 1992 Eastern of Well Televor location clearly and in accordinate with any State requirement of the surface 2 150' FSL and 2550' FEL AUG 2 7 1992 Eastern of Well Televor location clearly and in accordinate with any State requirement of the surface 2 150' FSL and 2550' FEL AUG 2 7 1992 Eastern of Well Televor location from nearest love or note office." 2150' FSL and 2550' FEL AUG 2 7 1992 Eastern of Well Televor location from nearest love or note office." 22 miles and direction from nearest love or note office." 23 miles and direction from nearest love or note office." 24 miles and direction from nearest love or note office." 25 miles and direction from nearest love or note office." 26 miles and direction from nearest love or note office." 27 miles and direction from nearest love or note office." 28 miles and direction from nearest love or note office." 28 miles and direction from nearest love or note office." 28 miles and direction from nearest love or note office." 29 miles and direction from nearest love or note office." 20 miles and direction from nearest love or note office." 20 miles and direction from nearest love or note office." 20 miles and direction from nearest love or note office. 20 miles and direction from nearest love or note office. 20 miles and direction from nearest love or note office. 21 miles and direction from nearest love or note office. 22 miles and direct	011 (1	. —		Single (Mu)	itiple (
Denver, CO 80210 Permit CO Inc. Denver Co Read Inc. Division CF San Juan Utar Division CF Division CF San Juan Utar Division CF Division CF San Juan Utar Division CF Division	· · · · · · · · · · · · · · · · · · ·				ie L		
Denver CO 80210 #3-5 Permit Co Inc.		•			I-1 _ <u> </u>		i rederar
Permitto Inc. Denvers CO 86 Land Carbon Field Section of Well Report location clearly and in accordance with any State requirements. 2150' FSL and 2550' FEL AUG 2 7 1992 Sec. 3, 7385 - R24E Distance in miles and direction from nearest town or post office' 2150' FSL and 2550' FEL AUG 2 7 1992 Sec. 3, 7385 - R24E Distance in miles and direction from nearest town or post office' 22 miles southeast of Monticello, UT Distance from proposed locations' 10. No. of abstluctages Minimized of accessing and Utah Distance from proposed locations' 10. No. of abstluctages Minimized of accessing and Utah Distance from proposed locations' 10. No. of abstluctages Minimized of accessing and Utah Distance from proposed locations' 10. No. of abstluctages Minimized of accessing and Utah Distance from proposed locations' 10. No. of abstluctages Minimized of accessing and Utah Distance from proposed locations' 10. No. of abstluctages Minimized of accessing and Utah Distance from proposed locations' 10. No. of abstluctages Minimized of accessing and Utah Distance from proposed locations' 10. No. of abstluctages Minimized of accessing and Utah Distance from proposed locations' 10. No. of abstluctages Minimized of accessing and Utah Distance from proposed locations' 10. No. of abstluctages Minimized of accessing and Utah Distance from proposed locations' 10. No. of abstluctages Minimized of accessing and Utah 10. No. of abstluctages Minimized of accessing and Utah 10. No. of abstluctages Minimized of accessing and Utah 10. No. of abstluctages Minimized of accessing and Utah 10. No. of abstluctages Minimized of accessing and Utah 10. No. of abstluctages Minimized of accessing and Utah 10. No. of abstluctages Minimized of accessing and Utah 10. No. of abstluctages Minimized of accessing and Utah 10. No. of abstluctages Minimized of accessing and Utah 10. No. of abstluctages Minimized of accessing and Utah 10. No. of abstluctages Minimized of accessing and Utah 10. No. of abstluctages Minimized of							•
Distance from proceeding the first processor of Well (Report location clearly und in accordance with any State requirement). AUG 2 7 1992 Sec. 3, T.S.R., M. or Bilk. Sec. 3, T.S.R. or Bilk. Sec. 3, T.S.R., M. or Bilk. Sec. 3, T.S.R., M. or Bil	Address of Operator	303/452-8888	13585 Jacks	son Orivez			Wildont
2150' FSL and 2550' FEL AUG 2 7 1992 Sec. 13, 138S - R24E AUG 2 7 1992 Sec. 3, 138S - R24E AUG 2 7 1992 Sec. 3, 138S - R24E Sec. 3, 138S - R24E AUG 2 7 1992 Sec. 3, 138S - R24E AUG 2 7 1992 Sec. 3, 138S - R24E AUG 2 7 1992 Sec. 3, 138S - R24E Sec. 3, 138S - R24E AUG 2 7 1992 Sec. 12, 138, 138, 138, 148 Aug 2 7 1992 Sec. 12, 138, 148 Aug 2 7 1992 Sec. 12, 138, 148 Aug 2 7 1992 Sec. 13, 138S - R24E Augustant and inches and inches to fixe and inches a	ocation of Well (Repor	t location clearly and in a	Donvon CO	0.000 0.000 0.000 0.000 0.000	MEIN	lá .	
Distance in miles and direction from nearest town or post offices 32 miles southeast of Monticello, UT 18. No. of abelianCRSS & Milhither of screen assigned bootston to nearest file. It. 18. No. of abelianCRSS & Milhither of screen assigned to this well bootston to nearest dire. It. 18. No. of abelianCRSS & Milhither of screen assigned to this well to this well to this well obstitute from preposed location. 18. No. of abelianCRSS & Milhither of screen assigned to this well to the total total to the total total to the total total total to the total	At surface			13 Com		. Sec., T., R., M., o	r Blk.
Distance in miles and direction from nearest town or post office* 32 miles southeast of Monticello, UT 12 Distance from proposed* 14 Distance from proposed* 15 No. of abeliances 1 Military or Partials 13. State San Juan 14 Utah 15 No. of abeliances 1 Military or Partials 13. State San Juan 15 No. of abeliances 1 Military or Carea assigned 16 No. of abeliances 1 Military or Carea assigned 17 No. of abeliances 1 Military or Carea assigned 18 Proposed depth (a No. of Abeliances) 19 Proposed depth (b No. of Abeliances) 19 Proposed depth (b No. of Abeliances) 19 Proposed depth (b No. of Abeliances) 10 Rotary 11 No. of Abeliances 1 Military 12 No. of Abeliances 1 Military 13 No. of Abeliances 1 Military 14 No. of Abeliances 1 Military 15 No. of Abeliances 1 Military 16 No. of Abeliances 1 Military 17 No. of Abeliances 1 Military 18 No. of Abeliances 1 Military 19 No. of Abeliances 1 Military 10 No. of Abeliances 1 Military 10 No. of Abeliances 1 Military 11 No. of Abeliances 1 Military 12 No. of Abeliances 1 Military 13 No. of Abeliances 1 Military 14 October 1, 1992 15 No. of Abeliances 1 Military 16 No. of Abeliances 1 Military 17 No. of Abeliances 1 Military 18 No. of Abeliances 1 Military 19 No. of Abeliances 1 Military 19 No. of Abeliances 1 Military 19 No. of Ab	at proposed prod zone			ΔUG 2 7	1992	and Survey or Are	ea.
Distance from purposed! Distance from purposed docking! Distance for Pulsanlor State office use) Distance from purposed docking dockin	it proposet prod. zone	in or sec.	3		1772	Sec. 3, T38	S - R24E
Size of Hole Size of Casing Weight per Poot Setting Depth Setting De	Distance in miles and o	lirection from nearest town	or post office*	[7]!![7](A)	1	2. County or Parrish	13. State
Distance from proposed' Property of lease lies. ft. Also to nervest drik. line. if any) 90 ' 1289.44 40 Distance from proposed location' 19. Proposed depth 20. Rotary or cable tools or applied for, on this lease, ft. 6076' Rotary 90 Cotober 1, 1992 PROPOSED CASING AND CEMENTING PROGRAM Size of Hole Size of Casing Weight per Poot 12-1/4" 13-3/8" 48# 120' 10- surface 12-1/4" 8-5/8" 24# 2075' 1100 sx or suffic to circ 7-7/8" 5-1/2" 15.5# 6076' 400 sx or suffic to circ 7-7/8" 5-1/2" 15.5# 6076' 400 sx or suffic to cover of interest. Duncan Energy Company proposes to drill a well to 6076' to test the Ismay formation. productive, casing will be run and the well completed. If dry, the well will be plug and abandoned as per BLM and State of Utah requirements. See Onshore Order No. 1 attached. We realize that the above location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of 0il, Gas & Mining. This locates have been staked at non-standard footages in accord and season on topography and seismic considerations and we request that you grant approof an exception to spacing. Duncan Energy Company is the lessee of all of Sections 3 and 4, T385 - R24E. Consultant for Title Duncan Energy Company Proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowner program, if any. Consultant for Title Duncan Energy Company Paperoval Date Approval Date OF UTAH DIVISION OF OIL, GAS, AND MINNING	32 miles south	neast of Montice	JIO UT			San Juan	Utah
PROPOSED CASING AND CEMENTING PROGRAM Size of Hole Size of Casing PROPOSED CASING AND CEMENTING PROGRAM Size of Hole Size of Casing PROPOSED CASING AND CEMENTING PROGRAM Size of Hole Size of Casing PROPOSED CASING AND CEMENTING PROGRAM Size of Hole Size of Casing Weight per Toot Setting Denth Quantity of Cement 17-1/2" 13-3/8" 48# 120' To surface 12-1/4" 8-5/8" 24# 2075' 1100 sx or suffic to circ 7-7/8" 5-1/2" 15.5# 6076' 400 sx or suffic to cover of interest. Duncan Energy Company proposes to drill a well to 6076' to test the Ismay formation. productive, casing will be run and the well completed. If dry, the well will be plug and abandoned as per BLM and State of Utah requirements. See Onshore Order No. 1 attached. We realize that the above location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of Oil, Gas & Mini	Distance from proposed	itas con moncice	16. No.	of acres in Reases & M			· · · · · · · · · · · · · · · · · · ·
Distance from Proposed locations to nearest well, drilling, completed, proposed locations to nearest well, drilling, completed, or applied for, on this lease, ft. approx. 800' 6076' Rotary Elevations (Show whether DF, RT, GR, etc.) PROPOSED CASING AND CEMENTING PROGRAM Size of Hole Size of Casing Weight per Foot Setting Depath Quantity of Cement 17-1/2" 13-3/8" 48# 120' To surface 12-1/4". 8-5/8" 24# 2075' 1100 sx or suffic to circ 7-7/8" 5-1/2" 15.5# 6076' 400 sx or suffic to cover of interest. Duncan Energy Company proposes to drill a well to 6076' to test the Ismay formation. Productive, casing will be run and the well completed. If dry, the well will be plug and abandoned as per BLM and State of Utah requirements. See Onshore Order No. 1 attached. We realize that the above location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of 011, Gas & Mining. This locates was based on topography and seismic considerations and we request that you grant approf an exception to spacing. Duncan Energy Company is the lessee of all of Sections 3 and 4, T38S - R24E. ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new live zone. If proposal is to dirill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blocation program, If any. Consultant for Duncan Energy Company Date 8/25/92 This space for Federal or State office use) Approval Date OF UTAH DIVISION OF OIL, GAS, AND Milning	property or lease line, :	ft.	901	1289 ///	to this w		
Elevations (Show whether DF, RT, GR, etc.) PROPOSED CASING AND CEMENTING PROGRAM PROPOSED CASING AND CEMENTING PROGRAM Size of Hole Size of Casing Weight per Foot Setting Depth Quantity of Cement 17-1/2" 13-3/8" 48# 120' To Surface 12-1/4" 8-5/8" 24# 2075' 1100 sx or suffic to circ 7-7/8" 5-1/2" 15.5# 6076' 400 sx or suffic to cover of interest. Duncan Energy Company proposes to drill a well to 6076' to test the Ismay formation. productive, casing will be run and the well completed. If dry, the well will be plug and abandoned as per BLM and State of Utah requirements. See Onshore Order No. 1 attached. We realize that the above location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of 0il, Gas & Mining. This loc was based on topography and seismic considerations and we request that you grant appr of an exception to spacing. Duncan Energy Company is the lessee of all of Sections 3 and 4, T38S - R24E. ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new tive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give bloc where program, if any. Consultant for Title. Duncan Energy Company Date 8/25/92 APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS. AMD MINING	Distance from proposed	ne. if any)			20 Rotary o		
Elevations (Show whether DF, RT, GR, etc.) 22. Approx. date work will start* October 1, 1992 PROPOSED CASING AND CEMENTING PROGRAM Size of Hole Size of Casing Weight per Foot Setting Depth Quantity of Cement 17-1/2" 13-3/8" 48# 120' To Surface 12-1/4" 8-5/8" 24# 2075' 1100 sx or suffic to circ 7-7/8" 5-1/2" 15.5# 6076' 400 sx or suffic to cover of interest. Duncan Energy Company proposes to drill a well to 6076' to test the Ismay formation. productive, casing will be run and the well completed. If dry, the well will be plug and abandoned as per BLM and State of Utah requirements. See Onshore Order No. 1 attached. We realize that the above location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of 0il, Gas & Mining. This locates was based on topography and seismic considerations and we request that you grant approf an exception to spacing. Duncan Energy Company is the lessee of all of Sections 3 and 4, T38S - R24E. ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new two zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blow enter program, if any. Consultant for Title Duncan Energy Company Date 8/25/92 This space for Federal or State office use) APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS. AND MINING	to nearest well, drilling or applied for, on this	, completed, ease, ft. annrox S	ι 00 1				
Size of Hole Size of Casing Weight per Foot Setting Depth Quantity of Cement 17-1/2" 13-3/8" 48# 120' To surface 12-1/4" 8-5/8" 24# 2075' 1100 sx or suffic to circ 7-7/8" 5-1/2" 15.5# 6076' 400 sx or suffic to cover of interest. Duncan Energy Company proposes to drill a well to 6076' to test the Ismay formation. productive, casing will be run and the well completed. If dry, the well will be plug and abandoned as per BLM and State of Utah requirements. See Onshore Order No. 1 attached. We realize that the above location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This loc was based on topography and seismic considerations and we request that you grant approof an exception to spacing. Duncan Energy Company is the lessee of all of Sections 3 and 4, T38S - R24E. ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new live zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blo enter program, if any. Consultant for Title Duncan Energy Company Date 8/25/92 APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AMD MINING			,00	0070	107		de coill near-be
PROPOSED CASING AND CEMENTING PROGRAM Size of Hole Size of Casing Weight per Foot Setting Depth Quantity of Cement 17-1/2" 13-3/8" 48# 120' To surface 12-1/4" 8-5/8" 24# 2075' 1100 sx or suffic to circ 7-7/8" 5-1/2" 15.5# 6076' 400 sx or suffic to cover of interest. Duncan Energy Company proposes to drill a well to 6076' to test the Ismay formation. productive, casing will be run and the well completed. If dry, the well will be plug and abandoned as per BLM and State of Utah requirements. See Onshore Order No. 1 attached. We realize that the above location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This loc was based on topography and seismic considerations and we request that you grant approof an exception to spacing. Duncan Energy Company is the lessee of all of Sections 3 and 4, T38S - R24E. ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new live zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give bloe enter program, if any. Consultant for Title Duncan Energy Company Date 8/25/92. APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING		, .v., GA, 800./				•	
Size of Hole Size of Casing Weight per Foot 17-1/2" 13-3/8" 48# 120' To surface 12-1/4": 8-5/8" 24# 2075' 1100 sx or suffic to circ 7-7/8" 5-1/2" 15.5# 6076' 400 sx or suffic to cover of interest. Duncan Energy Company proposes to drill a well to 6076' to test the Ismay formation. productive, casing will be run and the well completed. If dry, the well will be plug and abandoned as per BLM and State of Utah requirements. See Onshore Order No. 1 attached. We realize that the above location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This loc was based on topography and seismic considerations and we request that you grant appr of an exception to spacing. Duncan Energy Company is the lessee of all of Sections 3 and 4, T38S - R24E. ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new live zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give bio- enter program, if any. Consultant for Title Duncan Energy Company Date 8/25/92 APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS. AND MINING					·	Uctober 1,	1992
17-1/2" 13-3/8" 48# 120' To surface 12-1/4": 8-5/8" 24# 2075' 1100 sx or suffic to circ 7-7/8" 5-1/2" 15.5# 6076' 400 sx or suffic to cover of interest. Duncan Energy Company proposes to drill a well to 6076' to test the Ismay formation. productive, casing will be run and the well completed. If dry, the well will be plug and abandoned as per BLM and State of Utah requirements. See Onshore Order No. 1 attached. We realize that the above location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This loc was based on topography and seismic considerations and we request that you grant approf an exception to spacing. Duncan Energy Company is the lessee of all of Sections and 4, T38S - R24E. ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new live zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give bio enter program. If any. Consultant for Title. Duncan Energy Company Date. 8/25/92 APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING		P	ROPOSED CASING AND	CEMENTING PROGRAM	M		
17-1/2" 13-3/8" 48# 120' To surface 12-1/4" 8-5/8" 24# 2075' 1100 sx or suffic to circ 17-7/8" 5-1/2" 15.5# 6076' 400 sx or suffic to cover of interest. Duncan Energy Company proposes to drill a well to 6076' to test the Ismay formation. productive, casing will be run and the well completed. If dry, the well will be plug and abandoned as per BLM and State of Utah requirements. See Onshore Order No. 1 attached. We realize that the above location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This loc was based on topography and seismic considerations and we request that you grant approf an exception to spacing. Duncan Energy Company is the lessee of all of Sections 3 and 4, T38S - R24E. ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new live zone. If proposal is to deepen or plug back, give data on present productive zone and proposed new live zone. If proposal is to deepen or plug back, give data on present productive zone and proposed new live zone. If proposal is to deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give bio enter program, if any. Consultant for Title Duncan Energy Company APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING	Size of Hole	Size of Casing	Weight per Foot	Setting Depth		Quantity of Cemer	nt
12-1/4" 8-5/8" 24# 2075' 1100 sx or suffic to circ 7-7/8" 5-1/2" 15.5# 6076' 400 sx or suffic to cover of interest. Duncan Energy Company proposes to drill a well to 6076' to test the Ismay formation. productive, casing will be run and the well completed. If dry, the well will be plug and abandoned as per BLM and State of Utah requirements. See Onshore Order No. 1 attached. We realize that the above location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This located was based on topography and seismic considerations and we request that you grant approf an exception to spacing. Duncan Energy Company is the lessee of all of Sections 3 and 4, T38S - R24E. ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new live zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blocater program, if any. Consultant for Duncan Energy Company Date. 8/25/92 Consultant for Duncan Energy Company Date. 8/25/92 APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING	17-1/2"	13-3/8"			To sur		
7-7/8" 5-1/2" 15.5# 6076' 400 sx or suffic to cover of interest. Duncan Energy Company proposes to drill a well to 6076' to test the Ismay formation. productive, casing will be run and the well completed. If dry, the well will be plug and abandoned as per BLM and State of Utah requirements. See Onshore Order No. 1 attached. We realize that the above location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This located with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This located was based on topography and seismic considerations and we request that you grant approach of an exception to spacing. Duncan Energy Company is the lessee of all of Sections 3 and 4, T38S - R24E. ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new live zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blocated proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blocated proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blocated proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blocated proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blocated proposal is to drill or deepen directionally. Approval Date Consultant for Duncan Energy Company Approval Date Approval Date Approval Date Approval Date Approval Date Approval Date							to circ to
Of interest. Duncan Energy Company proposes to drill a well to 6076' to test the Ismay formation. productive, casing will be run and the well completed. If dry, the well will be plug and abandoned as per BLM and State of Utah requirements. See Onshore Order No. 1 attached. We realize that the above location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This located was based on topography and seismic considerations and we request that you grant approf an exception to spacing. Duncan Energy Company is the lessee of all of Sections 3 and 4, T38S - R24E. ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new live zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blocater program, if any. Consultant for Title Duncan Energy Company Date 8/25/92 APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING		<u>-</u>					
Duncan Energy Company proposes to drill a well to 6076' to test the Ismay formation. productive, casing will be run and the well completed. If dry, the well will be plug and abandoned as per BLM and State of Utah requirements. See Onshore Order No. 1 attached. We realize that the above location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This located was based on topography and seismic considerations and we request that you grant approof an exception to spacing. Duncan Energy Company is the lessee of all of Sections 3 and 4, T38S - R24E. ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new vive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blocated proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blocated proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blocated proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blocated proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blocated proposal is to drill or deepen directionally. Block proposal pate and proposed new formation pr	77.0	J 1/L	13.3π	0070			o cover zon
We realize that the above location has been staked at non-standard footages in accord with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This loc was based on topography and seismic considerations and we request that you grant approf an exception to spacing. Duncan Energy Company is the lessee of all of Sections 3 and 4, T38S - R24E. ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new tive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give bloventer program, if any. Consultant for Title Duncan Energy Company Date 8/25/92 APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING	and abandoned	as per BLM and	State of Utah r	completed. 1 requirements.	t dry, t	he well will	be plugged
with the spacing rules of the State of Utah, Division of Oil, Gas & Mining. This lock was based on topography and seismic considerations and we request that you grant approof an exception to spacing. Duncan Energy Company is the lessee of all of Sections 3 and 4, T38S - R24E. ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new live zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blocenter program, if any. Consultant for Title Duncan Energy Company Date 8/25/92 APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING							
Consultant for Title Duncan Energy Company Approval Date Approval Date Approval Date Duncan Energy Company Approval Date OF UTAH DIVISION OF OIL, GAS, AND MINING	with the spaci was based on t of an exception	ing rules of the topography and s on to spacing.	State of Utah. eismic consider	, Division of ations and we	Oil, Gas request	& Mining. that you gr	This locati ant approva
Consultant for Title Duncan Energy Company Approval Date Approval Date Approval Date Diverting and true vertical depths. Give blovened and true vertical depths. G							
Consultant for Title Duncan Energy Company Approval Date Approval Date Approval Date Discrete Signey Signey Signey Signey Signey Permit No. 13-037-31690 Approval Date Approval Date OF UTAH DIVISION OF OIL, GAS, AND MINING				,			4
Consultant for Duncan Energy Company (This space for Federal or State office use) Permit No. 43-037-31690 Approval Date OF UTAH DIVISION OF OIL, GAS, AND MINING	ABOVE SPACE DESCR	IBE PROPOSED PROGRA	M: If proposal is to deer	en or plug back, give d	ata on present	productive zone and	proposed new pro-
Consultant for Title Duncan Energy Company (This space for Federal or State office use) Permit No. 43-037-31690 Approval Date OF UTAH DIVISION OF OIL, GAS, AND MINING	enter program, if any.	to arm or deepen direction	nany, give pertinent data	on subsurface locations	and measured	and true vertical dep	ths. Give blowout
Title Duncan Energy Company (This space for Federal or State office use) Permit No. 43-037-31696 Approval Date OF UTAH DIVISION OF OIL, GAS, AND MINING			<u> </u>				
(This space for Federal or State office use) APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING		LI Duella					
Permit No. 43-037-31696 Approval Date APPROVED BY THE STATE OF UTAH DIVISION OF OIL, GAS, AND MINING	Signed Signed	() SIURE	Title Dur	ncan Energy Co	mpany	Date	8/25/92
Permit No. 4) - 0) 10 10 Approval Date OF UTAH DIVISION OF OIL, GAS, AND MINING	(This space for Federal	or State office use)			- Control of the second of the		Attendential statement
OIL, GAS, AND MINING	12-1	137- 311,A1	n		APPROV	IED BY THE	STATE
OIL, GAS, AND MINING	Permit No. 7	<u> </u>	<u>ب</u> A ₁	pproval Date	OF UT	FAH DIVISIO	N OF
Approved by Title							
Y X X X X X X X X X X X X X X X X X X X			Title	······································	•	/) The /c	TVIIVO
Conditions of approval, if any:	Conditions of approval, i	f any:		D)A E:	111311	-
BY: It lattheur				В	Y:	THY Int	theur
// ./0 # 9						ACINICAL	7-9-3
*See Instructions On Reverse Side WELL SPACING: 647-3-3			*See Instructions C	On Reverse Side	VELL SP	AUNG: 47	

Form 3160-3 (November 1983) (formerly 9-331C)

CONFIDENTIAL - TIGHT HOLE


SUBMIT IN PLICATE.

(Other insertions on reverse side)

Form approved.
Budget Bureau No. 1004-0136
Expires August 31, 1985

DEPARTMENT OF THE INTERIOR

BUREAU OF LAND MANAGEMENT APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK DRILL XX DEEPEN PLUG BACK	U-47876 6. IF INDIAN, ALLOTTEE OR TRIBE NAME N/A
DRILL XX DEEPEN DEPEN PLUG BACK	N/A
DRILL 🖾 DEEPEN 🗌 PLUG BACK 🗀	
	7. UNIT AGREEMENT NAME
b. TIPE OF WELL	
OIL XX GAS SINGLE XX MULTIPLE ZONE ZONE ZONE	Cave Canyon Unit 8. FARM OR LEASE NAME
2. NAME OF OPERATOR 303/759-3303 1777 S. Harrison St., PH-1	Cave Canyon Federal
Duncan Energy Company Denver, CO 80210	9. WELL NO.
ADDRESS OF OPERATOR 303/452-8888 13585 Jackson Drive	#3-5
Permitco Inc Agent Denver, CO 80241 L LOCATION OF WELL (Report location clearly and in accordance with any State requirements.*)	10. FIELD AND POOL, OR WILDCAT
At surface 2150' FSL and 2550' FEL TOTAL AT STATE OF THE	Cave Canyon Field 11. SEC., T., B., M., OR BLK.
At proposed prod. zone NW SE Sec. 3	Sec. 3, T38S - R24E
4. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE. ALLO O 7 4000	12. COUNTY OR PARISH 13. STATE
32 miles southeast of Monticello, UT AUG 2 7 1992	San Juan - Utah
5. DISTANCE FROM PROPOSED 17. NO. OF ACRES IN LEASE 17. NO. OF LOCATION TO NEAREST TO THE	F ACRES ASSIGNED
(Also to nearest drig. unit line, if any) (Also to nearest drig. unit line, if any)	40
S. DISTANCE FROM PROPOSED LOCATION TO NEAREST WELL, DRILLING, COMPLETED,	IY OR CABLE TOOLS MADE A STORY OF THE STORY
OR APPLIED FOR, ON THIS LEASE, FT. approx. 800 6076	Rotary
	22. APPROX. DATE WORK WILL START*
5218' GR 3.	0ctober 1, 1992
PROPOSED CASING AND CEMENTING PROGRAM	
SIZE OF HOLE SIZE OF CASING SETTING DEPTH	QUANTITY OF CEMENT
	rface
7-7/8" 5-1/2" 15.5# 6076' 400 s	<pre>sx or suffic to circ to su x or suffic to cover zones terest.</pre>
Duncan Energy Company proposes to drill a well to 6076' to test the productive, casing will be run and the well completed. If dry, the and abandoned as per BLM and State of Utah requirements.	e well will be plugged
See Onshore Order No. 1 attached.	Province to topics and two laws and
Be advised that Duncan Energy Company is considered to be the operand is responsible under the terms and conditions of the lease for on the leased lands.	ator of the above well the operations conducted
Bond coverage for this well is provided by BLM Bond CO-0959 (Princ Company) via surety consent as provided for in 43 CFR 3104.3. It BLM will hold the aforementioned operator and bond liable until the 3106.7-2 continuing responsibility are met.	is understood that the e provisions of 43 CFR
ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present production. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured eventer program, if any.	ctive sone and proposed new productive and and true vertical depths. Give blowout
SIGNED SEE CONSULTANT FOR TITLE DUNCAN Energy Company	DATE 8/25/92
(This space for Federal or State office use)	
(And Space for Account of State Omice date)	
PERMIT NO APPROVAL DATE	



WELL LOCATION DESCRIPTION:
R. T. DUNCAN, Cave Canyon, 3 - 5
2150'FSL & 2550'FEL
Section 3, T.38 S., R.24 E., SLM
San Juan, UT.
5218' ground elevation

The above plat is true and correct to my knowledge

29 May 1990

Gerald G. Huddlespones TON:

Gerald G. Huddlespones Tone

Gerald G. Huddle

and belie

PLAT #1

ONSHORE OIL & GAS ORDER NO. 1

Approval of Operations on Onshore Federal and Indian Oil and Gas Leases

CAVE CANYON FEDERAL #3-5 2150' FSL and 2550' FEL Section 3, T38S - R24E San Juan County, Utah

Prepared For:

DUNCAN ENERGY COMPANY

By:

PERMITCO INC. 13585 Jackson Drive Denver, Colorado 80241 303/452-8888

Copies Sent To:

- 4 BLM Moab, Utah
- 1 Div. of Oil, Gas & Mining SLC, Utah
- 3 Duncan Energy Company Denver, CO



TABLE OF CONTENTS <u>Cave Canyon #3-5</u>

DRILLING	PROGRAM	Page No.
1.	Formation Tops	1
2.	Anticipated Depth of Oil, Gas & Water	1
3.	Blow Out Preventer Requirements	2
4.	Casing and Cement Program	2-3
5.	Mud Program	3
6.	Testing, Logging and Coring	3-4
7.	Abnormal Pressures & H ₂ S Gas	4
8.	Other Information & Notification Requirements	4-6
SURFACE	USE PLAN	
1.	Existing Roads	1
2.	Access Roads to be Constructed or Reconstructed	1-2
3.	Location of Wells Within 1-Mile	2
4.	Proposed Production Facilities	2-3
5.	Water Supply	4
6.	Construction Materials	4
7.	Waste Disposal	4-5
8.	Ancillary Facilities	5
9.	Wellsite Layout	5-6
10.	Reclamation	6
11.	Surface/Minerals Ownership	7
12.	Other Information	7-9
13.	Certification	9



ONSHORE OIL & GATORDER NO. 1

CONFIDENTIAL - TIGHT HOLE

Duncan Energy Company <u>Cave Canyon Federal #3-5</u> 2150' FSL and 2550' FEL NW SE Sec. 3, T38S - R24E San Juan County, Utah

Drilling Program
Page 1

ONSHORE OIL & GAS ORDER NO. 1 Approval of Operations on Onshore Federal and Indian Oil and Gas Leases

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Orders, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance.

1. The surface formation and estimated formation tops to be encountered are as follows:

Formation	<u>Depth</u>	<u>Subsea</u>
Dakota	Surface	
Hermosa Group	698'	+ 533'
Ismay	5698'	- 467'
Upper Ismay Porosity	5749'	- 518'
Lower Ismay	5870'	- 639'
Gothic Shale	5917'	- 686'
Desert Creek	- 5944'	- 713'
Lower Desert Creek Por.	6001'	- 770'
Chimney Rock Shale	6020'	- 789'
Akah	6043'	- 812'
T.D.	6076'	- 845'

2. The estimated depths at which oil, gas, water or other mineral bearing zones are expected to be encountered are as follows:

Substance	Formation	Anticipated Depth
Oil	Ismay	5749'

All fresh water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth cased and cemented. All oil and gas shows will be tested to determine commercial potential.



ONSHORE OIL & GALE ORDER NO. 1
Duncan Energy Company
Cave Canyon Federal #3-5
2150' FSL and 2550' FEL
NW SE Sec. 3, T38S - R24E
San Juan County, Utah

Drilling Program
Page 2

3. Pressure control equipment will consist of a 10", 3000# BOP. (See BOP Diagram attached.)

BOP systems will be consistent with API RP 53. Pressure tests will be conducted before drilling out from under all casing strings which are set and cemented in place. Blowout preventer controls will be installed prior to drilling the surface casing plug and will remain in use until the well is completed or abandoned. Preventers will be inspected and operated at least daily o ensure good mechanical working order, and this inspection recorded on the daily drilling report. Preventers will be pressure tested before drilling casing cement plugs.

4. a. Casing

The proposed casing program is as follows: New or Purpose Depth **Hole Size** O.D. Wt. Grade Type Used Conductor 0-120' 17-1/2" 13-3/8" 48# New Surface 0-2075 12-1/4" 8-5/8" 24# K-55 ST&C New Produc. 0-6076 7-7/8" 5-1/2" 15.5# K-55 LT&C New

- b. If unconsolidated rock is encountered, conductor shall be set ten (10) feet into underlying bedrock with cement circulated to surface.
- c. Surface casing shall be set at least 50 feet into the Chinle Formation, regardless of the depth the Chinle is encountered.
- d. Cement

The cementing program will be as follows:

Conductor

0-120'

Type and Amount

Sufficient to circulate to surface

Surface Type and Amount

0-2075' 1100 sx or sufficient to circulate to surface.



COMPENTIAL - TIGHT HOLE

ONSHORE OIL & G. 3 ORDER NO. 1
Duncan Energy Company
Cave Canyon Federal #3-5
2150' FSL and 2550' FEL
NW SE Sec. 3, T38S - R24E
San Juan County, Utah

Drilling Program
Page 3

Production

Type and Amount

400 sx or - sufficient to cover zones of interest.

Anticipated cement tops will be reported as to depth, not the expected number of sacks.

- c. Auxiliary Equipment will be as follows:
 - 1. Kelly cock.
 - 2. Float above the bit.
 - 3. A sub with a full opening valve will be on the floor when the kelly is not in use.
- 5. Drilling fluid will be as follows:

<u>Interval</u>	Mud Type	Mud Wt.	Visc.	<u>F/L</u>	<u>PH</u>
0-4400'	Natural	9.0-9.2	35	10-20	
4400-T.D.	Chem. Gel	- 9.2-9.5	45	10 thru p	ays

Operations will be conducted in accordance with <u>ONSHORE OIL & GAS ORDER NO. 2</u>; <u>DRILLING OPERATIONS</u>, except where advance approval for a variance has been obtained.

- 6. Coring, logging and testing programs are as follow
 - a. No cores are anticipated.
 - b. The logging program will consist of the following: A Dual Induction will be run from 1800' to T.D. A BHC Acoustic and CNL/FDC will be run from 5500' to T.D.
 - c. No drill stem tests are anticipated.



ONSHORE OIL & CORDER NO. 1 **Duncan Energy Company**

Cave Canvon Federal #3-5 2150' FSL and 2550' FEL

NW SE Sec. 3, T38S - R24E San Juan County, Utah

DENTIAL - TIGHT HOLE

Drilling Program Page 4

Whether the well is completed as a dry hole or as a producer, "Well Completion or Recompletion Report and Log" (Form 3160-4) will be submitted to the District Office not later than thirty (30) days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1(b). Two copies of all logs, core descriptions, core analyses, well test data, geologic summaries, sample descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the Moab District Manager.

- 7. Abnormal conditions, bottom hole pressures and potential hazards.
 - The maximum bottom hole pressure to be expected is 2200 psi. a.
- **Anticipated Starting Dates and Notifications of Operations** 8.
 - Duncan Energy Company plans to spud the Cave Canyon Federal #3-5 on a. approximately October 1, 1992 and intends to complete the well within approximately one month after the well has reached T.D.
 - If a replacement rig is needed for completion operations, a Sundry Notice b. (Form 3160-5) to that effect will be filed for prior approval from the District Office, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig. In emergency situations. verbal approval to bring on a replacement rig will be approved through the District Office.
 - Required verbal notifications are summarized in Table I, attached. Written c. notification in the form of a Sundry Notice (Form 3160-5) will be submitted to the District Office within twenty four (24) hours after spudding. If the spudding occurs on a weekend or holiday, the written report will be submitted on the following regular work day.



ONSHORE OIL & G. ORDER NO. 1
Duncan Energy Company
Cave Canyon Federal #3-5
2150' FSL and 2550' FEL
NW SE Sec. 3, T38S - R24E
San Juan County, Utah

Drilling Program Page 5

- d. In accordance with Onshore Oil and Gas Order No. 1, this well will be reported on Form 3160-6, "Monthly Report of Operations", starting with the month in which operations commence and continuing each month until the well is physically plugged and abandoned. This report will be filed directly with Minerals Management Service.
- e. Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported to the Resource Area in accordance with requirements of NTL-3A.
- f. Should the well be successfully completed for production, the District Manager will be notified when the well is placed in producing status. Such notification will be sent by telegram or other written communication, not later than five (5) business days following the date on which the well is placed on production.
- g. A first production conference may be scheduled within fifteen (15) days after receipt of the first production report. The Resource Area Office will coordinate the field conference.
- h. A Subsequent Report of Abandonment" (Form 3160-5) will be filed with the District Manager within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the Area Manager or his representative, or the appropriate surface managing agency.
- i. Approval to vent/flare gas during initial well evaluation will be obtained from the District Office. This preliminary approval will not exceed 30 days or 50 MMCF gas. Approval to vent/flare beyond this initial test period will require District Office Approval pursuant to guidelines in NTL-4A.
- j. Upon completion of approved plugging, a regulation marker will be erected in accordance with 43 CFR 3162.6(d) and Onshore Oil and Gas Order No. 2.



ONSHORE OIL & GOORDER NO. 1
Duncan Energy Company
Cave Canyon Federal #3-5
2150' FSL and 2550' FEL
NW SE Sec. 3, T38S - R24E

San Juan County, Utah

CONDENTIAL - TIGHT HOLE

Drilling Program
Page 6

k. The following minimum information will be permanently placed on the marker with a plate, cap, or beaded-on with a welding torch:

Well name and number, location by 1/4 1/4 section, township and range, Lease number and operator.



While WAILE!	- ·
LOCATION :	<u> </u>
•	
~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	
9-5/8"	Circulating Line
Drilling Nipple / "	Stating Line
7-09	
BOR_BIG_Roms10 "x 3000 WR	
	-B.O.P. D. P. Roms 10 "x 3000 V/P
	Not Required
Check Volve 2 "x 3000 W.P.	
Volve 2" 3000 W.R.	Valve 2 " 3000 . W.P.
Valve 2 " 3000 WP 7	
are are are	The line 2 "Line
KILL LINE MANIFOLD	3000 WI
Spool 10 "x 3000 WP-	(See Exhibit "8")
Ground Level	

WELL HEAD B.O.P. 3000 #W.P.

⊠ Hydraulic

#### ONSHORE OIL & GAS ORDER NO. 1

**Duncan Energy Company Cave Canyon Federal 3-5** 

2150' FSL and 2550' FEL

NW SE Section 3, T38S - R24E

San Juan County, Utah

#### **CONFIDENTIAL - TIGHT HOLE**

Surface Use Plan Page 1

#### **Thirteen Point Surface Use Plan**

#### 1. Existing Roads

- a. The proposed well site is located 32 miles southeast of Monticello, Utah.
- b. Directions to the location from Monticello are as follows:

From the south edge of town go South on Highway 191 for 11.6 mile. Turn left (east) Alkali #204 (County Road) and proceed east and south for 3.1 miles to a fork in the road. Turn left and continue on Alkali #204 in a southeasterly direction for an additional 15 miles. Turn left (east) onto Perkins Road #206 and proceed 2.0 miles. Turn north onto an existing oilfield road and proceed approximately 800 feet to the #3-2 tank battery. Continue westerly for approximately 1000 feet to the proposed location.

- c. The roads in the area are primarily county roads. See Map #1.
- d. Improvement to the existing access will not be necessary.
- e. All existing roads will be maintained and kept in good repair during all drilling and completion operations associated with this well.
- f. An encroachment permit will be obtained from the San Juan County Road Department, 801/587-2231, ext. 43.

#### 2. Planned Access Roads

- a. There will be approximately 1000 for new access. This access was flagged at the time of staking.
- b. The maximum total disturbed width will be 30 feet.



#### ONSHORE OIL & GAS ORDER NO. 1

**Duncan Energy Company** 

Cave Canyon Federal 3-5

2150' FSL and 2550' FEL

NW SE Section 3, T38S - R24E

San Juan County, Utah

#### **CONFIDENTIAL - TIGHT HOLE**

Surface Use Plan
Page 2

- c. The maximum grade will be 6%.
- d. No turnouts will be necessary.
- e. One low water crossing will be necessary as shown on Map #1. A hard rock bottom exists at the crossing point.
- f. Surface disturbance and vehicular travel will be limited to the approved location and approved access route. Any additional area needed will be approved in advance by the surface owner.
- g. The access road (including any existing non-county) road will be brought to Resource (Class III) Road Standards by meeting the minimum design requirements within sixty (60) days of completion of drilling operations.
- h. All topsoil from the access road will be reserved in place.
- 3. <u>Location of Existing Wells Within a 1-Mile Radius of the Proposed Location.</u>
  (See Map #1).
  - a. Water Wells one
  - b. Injection or disposal wells one
  - c. Producing Wells four
  - d. Drilling Wells none
- 4. <u>Location of Tank Batteries and Production Facilities.</u>
  - a. All permanent structures (onsite for six months or longer) will be painted a neutral, nonreflective, (Juniper Green) color to blend into the



ONSHORE OIL & GAS ORDER NO. 1
Duncan Energy Company
Cave Canyon Federal 3-5
2150' FSL and 2550' FEL
NW SE Section 3, T38S - R24E
San Juan County, Utah

Surface Use Plan Page 3

surrounding area, except for those required to comply with the Occupational Safety and Health Act (OSHA) or written company safety manual or documents.

- b. If a tank battery is constructed on this location, it will be surrounded by a dike of sufficient capacity to contain 1-1/2 times the storage capacity of the largest tank; all load lines and valves will be placed inside the dike surrounding the tank battery.
- c. All site security guidelines identified in 43 CFR 3162.7-5 and <u>ONSHORE</u> <u>OIL & GAS ORDER NO. 3; SITE SECURITY</u> will be adhered to.
- d. Gas measurement will be conducted in accordance with the <u>ONSHORE</u>
  <u>OIL & GAS ORDER NO. 5; GAS MEASUREMENT</u> and 43 CFR
  3162.7-3.
- e. Gas meter runs for each well will be located within five hundred (500) feet of the wellhead. The gas flowline will be buried from the wellhead to the meter and downstream for the remainder of the pad. Meter runs will be housed and/or fenced.
- f. Oil measurement will be conducted in accordance with <u>ONSHORE OIL</u> & GAS ORDER NO. 4; OIL MEASUREMENT as of the effective date of August 23, 1989 and 43 CFR 3162.7-2.
- g. If the well is productive, the production facilities will be located at a central tank battery located at the Cave Canyon #3-2 in the NE SW Section 3, T38S R24E, San Juan County, Utah.
- h. Any necessary pits will be properly fenced to prevent any wildlife entry. The production pit will be flagged overhead.



#### ONSHORE OIL & GAS ORDER NO. 1 <u>CONFIDENTIAL - TIGHT HOLE</u>

Duncan Energy Company

<u>Cave Canyon Federal 3-5</u>

2150' FSL and 2550' FEL

NW SE Section 3, T38S - R24E

San Juan County, Utah

Surface Use Plan Page 4

#### 5. <u>Location and Type of Water Supply</u>

- a. All water needed for drilling purposes will be obtained from the Cave Canyon Water Source well located approximately 80 feet SW of the Cave Canyon #3-2 producing well. Other water may be obtained from the Richard Gore Artesian wells.
- b. Water will be trucked to location over the county roads in the area.
- c. No water well is to be drilled on this lease.
- d. Use of water for this operation will approved by obtaining a temporary use permit from the Utah State Engineer, in Price, Utah, 801/637-1303,
- e. Water obtained on private land, or land administered by another agency, will require approval from the owner or agency for use of the land.

#### 6. Source of Construction Material

- a. Road surfacing material will be obtained from on-site and in place materials.
- b. The use of materials under BLM jurisdiction will conform t 43 CFR 3610.

#### 7. <u>Methods for Handling Waste Disposal</u>

- a. The reserve pit will be constructed with at least 1/2 of the capacity in cut material and will be lined with 24 tons of bentonite.
- b. Three sides of the reserve pit will be fenced within 24 hours after completion of construction and the fourth side within 24 hours after



ONSHORE OIL & GAS ORDER NO. 1 Duncan Energy Company Cave Canyon Federal 3-5 2150' FSL and 2550' FEL NW SE Section 3, T38S - R24E San Juan County, Utah

Surface Use Plan Page 5

drilling operations cease with four (4) strands of barbed wire, or woven wire topped with barbed wire to a height of not less than four (4) feet. The fence will be kept in good repair while the pit is drying.

- c. No liquid hydrocarbons (i.e. fuels, lubricants, formation) will be discharged to the reserve pit.
- d. No chrome compounds will be on location.
- e. All trash will be placed in a trash basket and hauled to a county refuge facility as necessary.
- f. Produced waste water will be confined to the reserve pit for a period not to exceed ninety (90) days after initial production. During the 90-day period, an application for approval of a permanent disposal method and location, along with the required water analysis, will be submitted for the District Manager's approval pursuant to NTL-2B.

#### 8. Ancillary Facilities

a. There are no airstrips, camps, or other facilities planned during the drilling of the proposed well.

#### 9. Well Site Layout

- a. See Diagram #1 for rig layout. See Diagram #2 for cross section of drill pad. See Diagram #3 for cuts and fills.
- b. The location of mud tanks; reserve, trash cage; pipe racks; living facilities and soil stockpiles will be shown on Diagrams #1 and #3. The location will be laid out and constructed as discussed during the predrill conference.



ONSHORE OIL & GAS ORDER NO. 1
Duncan Energy Company
Cave Canyon Federal 3-5
2150' FSL and 2550' FEL
NW SE Section 3, T38S - R24E
San Juan County, Utah

Surface Use Plan Page 6

- c. 12 inches of topsoil material will be removed and stockpiled on the uphill side of the location as shown on Diagrams #1 & #3.
- d. Access to the well pad will be as shown on Map #1.

#### 10. Reclamation

- a. Within 24 hours of completion of drilling, the location and surrounding area will be cleared of all remaining debris, materials, and junk not required for production.
- b. As soon as the reserve pit has dried or within eighteen (18) months whichever is least, all areas not needed for production (including access road) will be filled in, recontoured to approximately natural contours and 12 inches of topsoil replaced leaving enough for future restoration (unless the well is a dry hole). The remaining topsoil (if any) will be stableized and seeded in place.
- c. The area will be seeded between October 1 and February 28 with:
  - 3 lbs/acre Indian Ricegrass
  - 8 lbs/acre Crested wheatgrass
  - 5 lbs/acre Fourwing saltbush
  - 3 lbs/acre Forage Kochia

Prior to seeding the location will be ripped 12 inches deep and 18 inches apart after recontouring. After broadcasting of seed a light harrow will be dragged over the location the bury the seed. If the seed is drilled, the seeding rate may e 75% of the above rates. Water bars may be required upon rehabilitation at the discrection of the Authorized Officer.

h. The reserve pit and that portion of the location and access road not needed for production and production facilities will be reclaimed.



ONSHORE OIL & GAS ORDER NO. 1
Duncan Energy Company
Cave Canyon Federal 3-5
2150' FSL and 2550' FEL
NW SE Section 3, T38S - R24E
San Juan County, Utah

Surface Use Plan Page 7

#### 11. a. Surface Ownership

**Bureau of Land Management** 

b. Mineral Ownership

**Bureau of Land Management** 

#### 12. Other Information

- a. There will be no deviation from the proposed drilling and/or workover program without prior approval from the District Manager. Safe drilling and operating practices must be observed. All wells, wheter drilling producing, suspended, or abandoned and/or separate facilities, will be identified in accordance with 43 CFR 3162.6.
- b. "Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.6.
- c. The dirt contractor will be provided with an approved copy of the surface use plan.
- d. An archeological study was conducted by LaPlata Archaeological Consultants. No significant cultural resources were found and clearance is recommended. A copy of this report will be submitted directly by LaPlata Archeological Consultants.
- e. The operator is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during



ONSHORE OIL & GAS ORDER NO. 1
Duncan Energy Company
Cave Canyon Federal 3-5
2150' FSL and 2550' FEL
NW SE Section 3, T38S - R24E
San Juan County, Utah

Surface Use Plan Page 8

construction, the operator is to immediately stop work that might further disturb such materials, and contact the authorized officer (AO). Within five working days the AO will inform the operator as to:

- whether the materials appear eligible for the National Register of Historic Places:
- the mitigation measures the operator will likely have to undertake before the site can be used (assuming in situ preservation is not necessary); and,
- a timeframe for the AO to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the AO are correct and that mitigation is appropriate.
- f. If the operator wishes, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the AO will assume responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise, the operator will be responsible for mitigation costs. The AO will provide technical and procedural quidelines for the conduct of mitigation. Upon verification from the AO that the required mitigation has been completed, the operator will then be allowed to resume construction.
- g. This permit will be valid for a period of one year from the date of approval. After permit termination, a new application will be filed for approval for any future operations.
- h. If at any time the facilities located on public lands authorized by the terms of the lease are no longer included in the lease (due to a contraction in the unit or other lease or unit boundary change) the BLM will process a change in authorization to the appropriate statute. The authorization will be subject to appropriate rental, or other financial obligation determined by the authorized officer.



# ONSHORE OIL & GAS ORDER NO. 1 Duncan Energy Company Cave Canyon Federal 3-5 2150' FSL and 2550' FEL NW SE Section 3, T38S - R24E San Juan County, Utah

#### **CONFIDENTIAL - TIGHT HOLE**

Surface Use Plan Page 9

i. In order to protect important deer winter range; exploration, drilling, and other development activity will be allowed only during the priod from April 1 to November 30. Exceptions to this limitation in any year may be specifically authorized in writing by the District Engineer, Geological Survey, with the concurrence of the District Manager, Bureau of Land Management.

#### 13. Lessee's or Operator's Representative and Certification

Permit Matters
PERMITCO INC.
Lisa L. Smith
13585 Jackson Drive
Denver, CO 80241
303/452-8888

Drilling & Completion Matters
DUNCAN ENERGY COMPANY
1777 S. Harrison St.
Penthouse One
Denver, CO 80210
303/759-3303 (W) 303/733-3604 (H) - John Bettridge

#### Certification

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which presently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and, that the work associated with the operations proposed herein will be performed by Duncan Energy Company and its contractors and subcontractors in conformity with the plan and the term and conditions under which it is approved.

This statement is subject to the provision of 18 U.S.C. 1001 for the filing of a false statement.

August 25, 1992

Date:


Lisa L. Smith - PERMITCO INC.

Authorized Agent for:

**DUNCAN ENERGY COMPANY** 







Scale 1"-50'

Diagram #1
Raymond T. Duncan
Cave Canyon #3-5
2150' FSL & 2550' FEL
Section 3, T38S - R24E
San Juan County, Utah

Cross Section

Raymond T. Duncan
Cave Canyon #3-5
2150' FSL & 2550' FEL
Section 3, %38S - R24E
San Juan County, Utah

Cut //// Fill --

1"=50' Horz. & Vert.

L....


C

c ¹



Ь

þ'



# ARCHAEOLOGICAL SURVEY OF RAYMOND T. DUNCAN'S CAVE CANYON FEDERAL 3-5 WELL PAD AND ACCESS ROAD SAN JUAN COUNTY, UTAH

# LAC REPORT 9076b

By Steven L. Fuller

LA PLATA ARCHAEOLOGICAL CONSULTANTS
P.O. BOX 783
DOLORES, COLORADO 81323
(303) 882-4933

June 4, 1990

FEDERAL ANTIQUITIES PERMIT 89UT57626 UTAH STATE PERMIT U90-LA-218b

Prepared for:

Raymond T. Duncan 1777 South Harrison, Penthouse 1 Denver, Colorado 80210

# **ABSTRACT**

The archaeological survey of Raymond T. Duncan's Cave Canyon Federal 3-5 well pad and access road was conducted by personnel of La Plata Archaeological Consultants on May 30, 1990. The project is located in San Juan County, Utah on lands administered by the Bureau of Land Management, San Juan Resource Area. A 100 foot wide corridor was surveyed along the 1000 foot access road and a 650 by 650 foot area (10 acres) was surveyed surrounding the well center stake. No archaeological sites were recorded during this survey and archaeological clearance is recommended for the project.

# INTRODUCTION


On May 30, 1990 the archaeological survey of Raymond T. Duncan's Cave Canyon Federal 3-5 well pad and access road was conducted by Steven L. Fuller of La Plata Archaeological Consultants. The survey was requested by Ms. Lisa Smith of Permitco, who was acting as a permit agent for Raymond T. Duncan. The well pad and access road are on lands administered by the Bureau of Land Management, San Juan Resource Area and are in San Juan County, Utah.

The project is located in T38S, R24E, Section 3, SE 1/4 and SW 1/4. The project is included on the USGS Bradford Canyon, Utah (1985 provisional) 7.5' series topographic map (Figure 1). The project will involve construction of a well pad which will measure about 300 by 230 feet, and about 1000 feet of access road which will extend from an existing oilfield road to the southwest. A total of 12.3 acres were examined for this project.

# PHYSIOGRAPHY AND ENVIRONMENT

The project area is located in Cave Canyon, on an open bench to the northwest of the canyon bottom. Sandstone outcrops rise to the northwest and the topography drops off gently to the southeast into the Cave Canyon wash bottom. Soils are very shallow and are formed on residual shale and sandstone deposits. Vegetation consists of grasses, snakeweed, shadscale, with sparse pinyon and juniper to the northwest on sandstone outcrops and ridges.

The present land use pattern includes livestock grazing and oil and gas development. The closest water sources are probably springs and seeps in Cave Canyon.



# **SURVEY PROCEDURES**

The official file search was conducted with the BLM files located in the San Juan Resource Area Office on May 29, 1990. This search indicated that numerous archaeological surveys have been conducted in the vicinity of the project area, primarily several well pad surveys conducted by La PLata for Raymond T. Duncan. Several seismic lines have also been surveyed by AERC, DCA, and La Plata during the early and mid-1980s. The nearest previously recorded site, 42SA14614, appeared to have been recorded on the east edge of the survey area but was probably mislocated on the old 15' map and probably is 400 or 500 feet to the northeast in some boulders. The site will not be affected by this proposed project.

The on-the-ground survey consisted of walking a zigzag transect down one side of the access road centerline and returning down the opposite side. A total width of 100 feet was covered with transect spacing averaging 50 feet or about 15 m. The proposed alignment was flagged during the final archaeological survey. Parallel pedestrian transects spaced about 15 m apart were used to cover the 650 by 650 foot (10 acre) area surrounding the well center stake.

The access road and well pad together contain a total of 12.3 acres which were inventoried for cultural resources for this project. All acreage is administered by the Bureau of Land Management, San Juan Resource Area.

# **SURVEY RESULTS**

No cultural resources were found during the survey for this proposed well pad, access road, and pipeline and it is unlikely that buried cultural deposits are present.

# CONCLUSIONS AND RECOMMENDATIONS

The archaeological survey for Raymond T. Duncan's Cave Canyon Federal 3-5 access road and well pad was conducted on May 30, 1990 by personnel of La Plata Archaeological Consultants. The project is located on lands administered by the Bureau of Land Management, San Juan Resource Area. No cultural resources were found and archaeological clearance is recommended for the project.

# Application for Right-of-Way Encroachment Pormit

DATE:	8/25/92		s (	and the second of		*	
TO:		rvisor County Road					*
Appli	cation is l	hereby made	by: (1) Du	and the second s		c/o PERMITCO I	NC.
Addre	ess (2) 13	585 Jackson	Drive Den	ver, CO 8	0241		
Telep	phone Number	r: 303/452-	8888	for pe	ermission to	o do the follo posed drillsite	wing:
•	located as			**************************************	**************************************		
<del></del>	Cave Canvon	Fed #3-5	2150! FSI	and 2550!	EEL MUSE	Sec. 3, T38S -	Dalic
	save sanyon	: <u>''</u>	2150-131	and 2550	FEL, NW.SE	sec. 3, 1305 -	KZ4E
		Approximat				ello, Utah.	***************************************
Ro	ads to be u	sed will be	Alkali #20	4 and Perk	ins #206.		
. Pr	oposed spud	l date is Oc		192			
				<del></del>	2 (4	State U	tah
or U.	S. Highway	No.	· .	Milepos	t No.	<b>.</b>	
in ac	cordance wi	th the atta	nched plan.	(5)	and the second second	,	
		ı will begir				19	
	2	for the same			(4) (1) (2) (2)	19	
	A 188	posed insta		The American	Mr. Oak Brown	ne pavement, g	ive
a. T	ype of pave	ement: N/A					
b. T	he opening	to be made	will be	N/A		feet lon	g
bу		feet wi	de and	.,	W. G.	feet deep.	
c. A	bond in th	e amount of	• <b>\$</b> N/	'A 445 45 #	has been	posted with	
				Tel	ephone No.		_
to ru satis	n of a term factory per	of three (formance.	3) years a		A Total Control of the Control of th	ork to guarante	
restr nad P Road adopt (8) effor the e which	iction, and rotection of Commission and by the S In approvint will be movent that S the utilit	regulation of State Hig on October an Juan Cou g this appl ade to appr	s as conta hway Right β, 1962, a nty Commis ication an ove only 1 nty change moved, th	ined in th s-of-Way*, nd all rev sion. d location ocations t s the road	e "Regulati approved h isions ther s of utilit hat will no way. But	l conditions, ons for the Cons for the Constant States or Regular ies, and it be effected in situations ne by the util	in
<i>(9)</i>	Pan a		•			Vibroseise,	

- Provide map showing where vibroseising will take place.
- Agree to repair any damages or replace any property damaged.
- Take full responsibility or proper flagging and traffic control.

A STREET TO JULY GRAPA

\$5.00 Filing Fee Attached.

- d. Agree that Vibroseising done in the area of dirt roads shall done on the dirt road rather than in the bar ditch to minimize damage.
- e. Provide a schedule of the planned work and estimated dates of completion.
- f. Attach written permission form all adjacent fee-title owners.
- g. The San Juan County Commission has authorized the San Juan County Road Superintendent (or his Assignees) to issue permits.
- (10) San Juan County can only grant permission to the extent that the County has the aurhority to do so and the permission granted hereunder is limited to the interest of authority actually owned by San Juan County and no warranties of ownership or authority to grant permission is expressed or implied by the granting of this permit.

BY: Lisa L. Smith - PERMITCO INC.

Authorized Agent for Duncan Energy Company
TITLE

To be filled in by Road Supervisor.

<i>(1)</i>	Permi t	should be	granted	***************************************	······································
	Permit	should not	t be gran	ited	

(2) Additional requirements which should be imposed.

ROAD	GHD	いわい	TCO	D .
		-21 V	120	п

#### INSTRUCTIONS

- (1) *Application for this permit should be made in duplicate by whoever will actually do the work whether it be the owner or a contractor.
- (2) Mailing address of applicant.
- (3) State fully and completely the type or installation, type of construction, width, thickness, drainage data, etc., where applicable. If pole line, give the following information: number of poles, total length of line, type of wire, character of service, vertical clearance over roadway, and voltage of power line.
- (4) If pipe line or buried cable, give the follwing information: Type of service, size and length of line, depth of trench, kind of pipe, (sewer, gas, oil, water supply, etc.) or conduit, and if pipe is to be driven or if pavement will be broken. All fluid lines requires encasement with suitable material. The size and length of encasement shall be satisfactory to the State Department of Transportation, San Juan County Road Supervisor or his agent.
- (5) Give distance from some geographical point such as intersecting highways, city, or coporate limits. Give city, county, and state or U. S. route number.
- (6) Attach two (2) copies of a plan showing proposed location of structures with reference ot pavement and right-of-way lines. If installation crosses the highway, show cross section of present roadway and proposed installation.
- (7) Give anticipated dates for beginning and for completion of proposed installation.

Note: A fee of five (5) dollars will be charged for all Right-of-Way Encroachments Permits, except those obtained for pole lines, and buried cable lines. This Permit fee, where applicable, should be submitted with the application. The costs of inspection are included in the Right-of-Way Encroachment Permit fee, except for pole lines, pipe lines, and buried cable lines which shall be billed for the inspection.

# WORKSHEET APPLICATION FOR PERMIT TO DRILL

OPERATOR: DUNCAN ENERGY COMPANY OPERATOR ACCT NO: N-3370 WELL NAME: CAVE CANYON FEDERAL 3-5 API NO. ASSIGNED: 43 -037 - 31696 LEASE NO: LEASE TYPE: FED LOCATION: NWSE 03 - T38S - R24E SAN JUAN COUNTY FIELD: UNDESIGNATED FIELD CODE: (30)3 LOCATION AND SITING: Cave Canyon Field

N R649-2-3. Unit: Secondary Recovery RECEIVED AND/OR REVIEWED: Plat Bond (Number R649-3-2. General. Potash (Y/N) Oil shale (Y/N)  $\hat{K}$ R649-3-3. Exception. Water permit (Number 09-1808) Drilling Unit. RDCC Review (Y/N) Board Cause no: (Date: Date: COMMENTS: STIPULATIONS: CONFIDENTIAL PERIOD

DATE RECEIVED: 08/27/92

DATE RECEIVED: 06/13/90

Form 3160-3 (November 1983) (formerly 9-331C) CONFIDENTIAL - TIGHT HOLE

(Other in cructions on reverse side) DEPARTMENT OF THE INTERIOR

RIPLICATE.

Form approved. Budget Bureau No. 1004-0136 Expires August 31, 1985

		OF THE IN			5. LEASE DESIGNATION AND SERIAL NO.
	BUREAU OF	LAND MANAGE	MENT		<u>U-47876</u>
APPLICATION	Y FOR PERMIT	TO DRILL DE	EPEN, OR PLUG	BACK	6. IF INDIAN, ALLOTTEE OR TRIBE NAME
1a. TYPE OF WORK		. 0 0 0 .		DACK	N/A
DR	ILL 🛛	DEEPEN 🗌	PLUG B	ACK []	7. UNIT AGREEMENT NAME
b. TYPE OF WELL			_		<u>Cave Canyon</u> Unit
WELL LAIX W	ELL OTHER	•	SINGLE XX MUL	TIPLE	S. FARM OR LEASE NAME
2. NAME OF OPERATOR	303/759-3303	1777 S. Har	rison St., PH-1		Cave Canyon Federal
Duncan Energy	Company	Denver, CO	80210		9. WELL NO.
3. ADDRESS OF OPERATOR	303/452-8888	13585 Jacks			#3-5
Permitco Inc.	- Agent	Denver CO	80241		10. FIELD AND POOL, OR WILDCAT
4. LOCATION OF WELL (R. At SULIGE	eport location clearly and	in accordance with	any State requirements.*)	<del></del>	Cave Canyon Field
at surface		L and 2550' F			11. SEC., T., R., M., OR BLK.
At proposed prod. zon	AUL CE C				AND SURVEY OR AREA
Proposed Prod. 202	02 00				Sec. 3, T38S - R24E
14. DISTANCE IN MILES	AND DIRECTION FROM NEAD	EST TOWN OR POST O	FFICE*		12. COUNTY OR PARISH   13. STATE
	theast of Monti				
15. DISTANCE FROM PROPU	SED*		S. NO. OF ACRES IN LEASE	1 17 NO 0	San Juan Utah
PROPERTY OR LEASE L	INE. PT		or seems in bear	TO TE	HIS WELL
(Also to nearest drig 18. DISTANCE FROM PROP	unit line, if any)	90'	1289.44		40
TO NEAREST WELL, DE OR APPLIED FOR, ON THE	RILLING, COMPLETED.	1	PROPOSED DEPTH	20. ROTAL	BY OR CABLE TOOLS.
	auurn	x. 800' l		ļ	Rotary
21. ELEVATIONS (Show whe	ther Dr. Kr. GR. etc.)				22. APPROX. DATE WORK WILL START*
23.					October 1, 1992
<b>43.</b>	P	ROPOSED CASING	AND CEMENTING PROG	RAM	
SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	1	QUANTITY OF CEMENT
17-1/2"	13-3/8"	48#	120'	TO SU	rface
12-1/4"	8-5/8"	24#	2075'		
7-7/8"	5-1/2"	15.5#	6076'	1100	sx or suffic to circ to su
the former of	, <del>-</del>	10.01	0070	1 400 S	x or suffic to cover zones




# **DIVISION OF** OIL GAS & MINING

one. If proposal is to drill or deepen directionally, give preventer program, if any.	and measured a	nd true vertical depths. Give blowe
SIGNED Soula	Consultant for  TITLE Duncan Energy Company	DATE <u>8/25/92</u>
(This space for Federal or State office use)		
PERMIT NO.	APPROVAL PATE	·
APPROVED BY /S/ WILLIAM C. STRINGER CONDITIONS OF APPROVAL, IF ANY:	Assistant District Manager  for Minerals	OCT 3 0 1992

FLARING OR VENTING OF GAS IS SUBJECT TO NTL 4-A

CONDENSAL LIEU MARKET ATTACHED

*See Instructions On Reverse Side Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



WELL LOCATION DESCRIPTION:
R. T. DUNCAN, Cave Canyon, 3 - 5
2150'FSL & 2550'FEL
Section 3, T.38 S., R.24 E., SLM
San Juan, UT.
5218' ground elevation

The above plat is true and correct to my knowledge

29 May 1990

Gerald G. Huddling Dones TON!

Suels Suesting Of The OF UT

and belie

Duncan Energy Company Cave Canyon Federal No. 3-5 NWSE Sec. 3, T.38S., R.24E. San Juan County, Utah Lease U-47876

# CONDITIONS OF APPROVAL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be advised that Duncan Energy Company is considered to be the operator of the above well and is responsible under the terms and conditions of the lease for the operations conducted on the leased lands.

Bond coverage for this well is provided by CO 0959 (Principal -Duncan Energy Company) via surety consent as provided for in 43 CFR 3104.2.

This office will hold the aforementioned operator and bond liable <u>until</u> the provisions of 43 CFR 3106.7-2 continuing responsibility are met.

This permit will be valid for a period of one year from the date of approval. After permit termination, a new application must be filed for approval.

All lease operations will be conducted in full compliance with applicable regulations (43 CFR 3100), Onshore Oil and Gas Orders, lease terms, notices to lessees, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions and the approved plan will be made available to field representatives to insure compliance.

# A. DRILLING PROGRAM

1. Daily drilling and completion progress reports shall be submitted to the District Office on a weekly basis.

# B. SURFACE USE PLAN

The bentonite will be worked into the soil of the reserve pit.

# C. REQUIRED APPROVALS, REPORTS AND NOTIFICATIONS

Required verbal notifications are summarized in Table 1, attached.

<u>Building Location</u>- Contact the Resource Area, Natural Resource Protection Specialist at lease 48 hours prior to commencing construction of location.

<u>Spud</u>- The spud date will be reported to the Resource Area Office 24 hours prior to spudding. Written notification in the form of a Sundry Notice (Form 3160-5) will be submitted to the District Office within 24 hours after spudding, regardless of whether spud was made with a dry hole digger or big rig.

<u>Daily Drilling Reports</u>- Daily drilling reports shall detail the progress and status of the well and shall be submitted to the District Office on a weekly basis.

Monthly Reports of Operations- In accordance with Onshore Oil and Gas Order No. 1, this well shall be reported on Minerals Management Service (MMS) Form 3160, "Monthly Report of Operations," starting the month in which operations commence and continuing each month until the well is physically plugged and abandoned. This report will be filed directly with MMS.

<u>Sundry Notices</u>- There will be no deviation from the proposed drilling and/or workover program without prior approval from the Assistant District Manager. "Sundry Notices and Reports on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2. Safe drilling and operating practices must be observed.

<u>Drilling Suspensions</u>-Operations authorized by this permit shall not be suspended for more than 30 days without prior approval of the Authorized Officer. All conditions of this approval shall be applicable during any operations conducted with a replacement rig.

<u>Undesirable Events</u>- Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be immediately reported to the Resource Area in accordance with requirements of NTL-3A.

<u>Cultural Resources</u>- If cultural resources are discovered during construction, work that might disturb the resources is to stop, and the Area Manager is to be notified.

<u>First Production</u>- Should the well be successfully completed for production, the Assistant District Manager, Minerals Division will be notified when the well is placed in producing status. Such notification may be made by phone, but must be followed by a sundry notice or letter not later than five (5) business days following the date on which the well is placed on production.

A first production conference will be scheduled as soon as production testing begins and hydrocarbons reach the surface. This conference should be coordinated through the Resource Area Office.

Well Completion Report- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted to the District Office not later than thirty (30) days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs, core descriptions, core analyses, well test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings and /or samples) will be submitted when requested by the Assistant District Manager.

<u>Venting/Flaring of Gas- NTL-4A</u> allows venting/flaring of gas during the initial well evaluation period not to exceed 30 days or 50 MMcf. Venting/flaring beyond the initial test period threshold must be approved by the District Office.

<u>Produced Water-</u> Produced waste water may be confined to an unlined pit for a period not to exceed 90 days after initial production. During the 90 day period, an application for approval of a permanent disposal method and location, along with the required water analysis, will be submitted to the Assistant District Manager for approval pursuant to NTL-2B.

Off-Lease Measurement, Storage, Commingling- Prior approval must be obtained from the Assistant District Manager for off-lease measurement, off-lease storage or commingling (either down-hole or at the surface).

<u>Plugging and Abandonment</u>- If the well is completed as a dry hole, plugging instructions must be obtained from the BLM, Moab District Office prior to initiating plugging operations. Table 1 of this document provides the after-hours phone numbers of personnel who are authorized to give plugging instructions.

A "Subsequent Report of Abandonment" (Form 3160-5) will be filed with the Assistant District Manager, Minerals Division within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Upon completion of approved plugging, a regulation marker will be erected in accordance with 43 CFR 3162.6. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the Area Manager or his representative, or the appropriate surface managing agency.

# **NOTIFICATIONS**

Notify Jeff Brown, Robert Larsen or Bob Turri of the San Juan Resource Area, at (801) 587-2141 for the following:

- 2 days prior to commencement of dirt work, construction or reclamation;
- 1 day prior to spudding;
- 50 feet prior to reaching surface casing setting depth;
- 3 hours prior to testing BOPE;

If the person at the above number cannot be reached, notify the Moab District Office at (801) 259-6111. If unsuccessful, notify one of the people listed below.

Well abandonment operations require 24 hour advance notice and prior approval. In the case of newly drilled dry holes, verbal approval can be obtained by calling the Moab District Office, Branch of Fluid Minerals at (801) 259-6111. If approval is needed after work hours, you may contact the following:

Eric Jones, Petroleum Engineer

Office: (801) 259-6111

Home: (801) 259-2214

If unable to reach the above individuals, please call the following:

Lynn Jackson,

Office: (801) 259-6111

Chief, Branch of Fluid Minerals Home: (801) 259-7990

# TEMPORARY Rec. by Fig. 13 1992 NOV 0 2 1992—CELYSTATE OF UTAH OIL GAS & MARCH ENGINE For the purpose of acquiring the real to deep portion of the unappropriated water of the State of Utah, application is hereby made to the State Engineer, based upon the following showing of facts, submitted in accordance with the requirements to Title 73, Chapter 3 of the Utah Code Annotated (1953, as amended). *WATER RIGHT NO. 09 - 1808 *APPLICATION NO. A T66548 1. *PRIORITY OF RIGHT: October 13, 1992 *FILING DATE: October 13, 1992 2. OWNER INFORMATION Name(s): Duncan Energy Company Address: 1777 S, Harrison Street, PH-1

TER RIGHT NO. 09 - 1808	-	*APPLICAT	TION NO. A	T6 <b>6</b> 548	
*PRIORITY OF RIGHT: October	13, 1992	*FILING	DATE:	October 13	, 1992
OWNER INFORMATION .					
Name(s): Duncan Energy Compan Address: 1777 S. Harrison Str	У		*Interest:_	100	9
Address: 1/// S. Harrison Str	eet, PH-I	<u></u>		00010	
CityBenver	State:	00	Zip Co	ode: 80210	
Is the land owned by the applicant? Yes					
QUANTITY OF WATER:	<u>.</u>	cfs and/or	5_		ac-f
SOURCE: Cave Canyon Wtr. Sou which is tributary to which is tributary to					
POINT(S) OF DIVERSION:		COUNTY:	San Juan		
North 1870 feet and East 187 T38S - R24E, SLB&M	O feet from	the Southwest	corner of	Section 3,	
				,	
Description of Diverting Works: 7" c *COMMON DESCRIPTION: 14 mile	es SE of Bla	unding		Blanding	Quad
Description of Diverting Works: 7" c *COMMON DESCRIPTION: 14 mile POINT(S) OF REDIVERSION The water will be rediverted from N/A				a	t a poin
POINT(S) OF REDIVERSION The water will be rediverted from N/A				a	t a poin
POINT(S) OF REDIVERSION The water will be rediverted from N/A  Description of Diverting Works:				a	t a poin
POINT(S) OF REDIVERSION The water will be rediverted from N/A  Description of Diverting Works:  POINT(S) OF RETURN	•			a	t a poin
POINT(S) OF REDIVERSION The water will be rediverted from N/A  Description of Diverting Works:  POINT(S) OF RETURN The amount of water consumed will be The amount of water returned will be	-0-	cfs or cfs or	5	a	t a poin
POINT(S) OF REDIVERSION The water will be rediverted from N/A  Description of Diverting Works:	-0- eam/source at a p	cfs or cfs or point(s):	5	a	t a poir
POINT(S) OF REDIVERSION The water will be rediverted from N/A  Description of Diverting Works:  POINT(S) OF RETURN The amount of water consumed will be The amount of water returned will be The water will be returned to the natural street.  STORAGE Reservoir Name: N/A	-0- earn/source at a p	cfs or cfs or ooint(s):	5	a	t a poin
POINT(S) OF REDIVERSION The water will be rediverted from N/A  Description of Diverting Works:  POINT(S) OF RETURN The amount of water consumed will be The water will be returned to the natural street.	-0- earn/source at a p	cfs or cfs or ooint(s):	5	a	t a poin ac-f

* These items are to be completed by the Division of Water Rights

**TEMPORARY** 

•	List any other water rights which will supplement to	ins application		
	NATURE AND PERIOD OF USE			
	Irrigation:	From	to	
	Stockwatering:		to	
	Domestic:		to	
	Municipal:		to	
	Mining:		to	
	Power:	From	to	
	Other: Oil Well Drilling	From Oct. 25, 19	to 92 to_December 15,	1992
0.	PURPOSE AND EXTENT OF USE Irrigation:acre Stockwatering (number and kind):			
	Domestic:	Families and/or	•	Persons.
	Municipal (name):			
	Mining: Mini	ing District in the		Mine.
	Ores mined:	<u> </u>		
	Power: Plant name: Other (describe): Duncan Energy Company	lype:	Capacity:	Cavo Canvo
	Unical Energy Company  Lease Waterflood Proj	pians www.intii t	wo orr werrs in the	cave carryor
	v	Jeur		
1.	PLACE OF USE			
	Legal description of place of use by 40 acre tract(s)	);	·	
	Cave Canyon #3-5 NW SE (2510' FSL	_ and 2550' FEL) S	ec. 3, T38S - R24E	- SLRAW
	O Us m sul sim I mod miss	1 10001	4 TAAA KAAB	C+ D 0 N4
<u>.</u>	Cave Canyon #4-5 NW NE (50' FNL a  EXPLANATORY	and 1800' FEL) Sec		
	EXPLANATORY The following is set forth to define more clearly the size if necessary):	e full purpose of this appliance proposes to drawaterflood project BW. Water will be a capacity of illsite is managed eral Government are Energy Company  ***********************************	cation. (Use additional pages ill two development. Water use to drive trucked or pumped 80-100 Bbls. and will by the Bureau of Lind the extraction ri	s of the same oil wells ll each to each ll be and Manageme ghts to the
	EXPLANATORY The following is set forth to define more clearly the size if necessary):	e full purpose of this appliancy proposes to drawaterflood project BW. Water will be ave a capacity of illsite is managed eral Government are Energy Company  ***********************************	cation. (Use additional page ill two development. Water use to drive trucked or pumped 80-100 Bbls. and will by the Bureau of Lind the extraction rimbat which can be beneficially ugh he/she/they may have been mployees of the Division of the ill was additional page.	s of the same oil wells ll each to each ll be and Managem ghts to the  ********  Itends to become used for the puren assisted in the Water Rights, all
	EXPLANATORY  The following is set forth to define more clearly the size if necessary):	e full purpose of this appliancy proposes to drawaterflood project BW. Water will be ave a capacity of illsite is managed eral Government are Energy Company  ***********************************	cation. (Use additional page ill two development. Water use to drive trucked or pumped 80-100 Bbls. and will by the Bureau of Lind the extraction riminated States of America or in hat which can be beneficially ugh he/she/they may have been mployees of the Division of the of filing, rests with the application.	s of the same oil wells ll each to each ll be and Managem ghts to the  ********  Itends to become used for the puren assisted in the Water Rights, all licant(s).
	EXPLANATORY The following is set forth to define more clearly the size if necessary):  Duncan Energy Compa as part of the Cave Canyon Lease well will be approximately 10,000 drillsite. The pump truck will have enclosed. The surface at each drithe minerals are owned by the Federal leases are owned by Duncar The applicant(s) hereby acknowledges that he/she/th such a citizen(s). The quantity of water sought to be poses herein described. The undersigned hereby acknowledges hereby acknowledges that he/she/th such a citizen(s). The quantity of water sought to be poses herein described. The undersigned hereby acknowledges have preparation of the above-numbered application through the such a citizen (s).	e full purpose of this appliany proposes to drawaterflood project BW. Water will be ave a capacity of illsite is managed eral Government are Energy Company  ***********************************	cation. (Use additional pages 111 two developments. Water use to drive trucked or pumped 80-100 Bbls. and will by the Bureau of Lind the extraction richat which can be beneficially ugh he/she/they may have been mployees of the Division of the of filing, rests with the applications of the state of the Applications of the property of	s of the same oil wells ll each to each ll be and Managem ghts to the  ********  Itends to become used for the puren assisted in the Water Rights, all licant(s).
	EXPLANATORY The following is set forth to define more clearly the size if necessary):	e full purpose of this appliany proposes to drawaterflood project BW. Water will be ave a capacity of illsite is managed eral Government are Energy Company  ***********************************	cation. (Use additional pages 111 two developments. Water use to drive trucked or pumped 80-100 Bbls. and will by the Bureau of Lind the extraction richat which can be beneficially ugh he/she/they may have been mployees of the Division of the of filing, rests with the applications of the state of the Applications of the property of	s of the same oil wells ll each to each ll be and Managem ghts to the  ********  Itends to become used for the puren assisted in the Water Rights, all licant(s).  ant(s)*  oration or
<b>2.</b>	EXPLANATORY The following is set forth to define more clearly the size if necessary):	e full purpose of this appliany proposes to drawaterflood project BW. Water will be ave a capacity of illsite is managed eral Government are Energy Company  ***********************************	cation. (Use additional page: ill two development Water use to dri be trucked or pumped 80-100 Bbls. and wi l by the Bureau of L id the extraction ri  *********************************  Juited States of America or in hat which can be beneficially ugh he/she/they may have bee mployees of the Division of the e of filing, rests with the application  Signature of Applications ust be the name of such corpor of the partners.	s of the same oil wells ll each to each ll be and Managem ghts to the  s*******  Intends to become used for the puren assisted in the Water Rights, all licant(s).  ant(s)*  oration orco Inc.

TEMPORARY

# STATE ENGINEER'S ENDORSEMENT

WATER RIGHT NUMBER: 09 - 1808

APPLICATION NO. T66548

1. October 13, 1992

Application received by MP.

2. October 19, 1992

Application designated for APPROVAL by MP and KLJ.

3. Comments:

Conditions:

This application is hereby APPROVED, dated October 30, 1992, subject to prior rights and this application will expire on October 30, 1993.

Robert L. Morgan

State Engineer





355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340

November 5, 1992

Duncan Energy Company 1777 S. Harrison St., PH-1 Denver, Colorado 80210

#### Gentlemen:

Re: Cave Canyon Federal #3-5 Well, 2150 feet from the south line, 2550 feet from the east line, NW 1/4 SE 1/4, Section 3, Township 38 South, Range 24 East, San Juan County, Utah

Pursuant to Utah Code Annotated Section 40-6-7 and 40-6-8 (1953 As amended); the order issued by the Board of Oil, Gas and Mining in Cause No. 217-1 dated June 23, 1989, for the Cave Canyon Field Secondary Recovery Unit; and Utah Administrative R. 649-3-4, Permitting of Wells to be Drilled, Deepened or Plugged-back, approval to drill the referenced well is hereby granted.

In addition, the following specific actions are necessary to fully comply with this approval:

- 1. Compliance with the requirements of Utah Admin. R. 649-1 et seq., Oil and Gas Conservation General Rules.
- 2. Notification within 24 hours after drilling operations commence.
- 3. Submittal of Entity Action Form, Form 6, within five working days following commencement of drilling operations and whenever a change in operations or interests necessitates an entity status change.
- 4. Submittal of the Report of Water Encountered During Drilling, Form 7.
- 5. Prompt notification prior to commencing operations, if necessary, to plug and abandon the well. Notify Frank R. Matthews, Petroleum Engineer, (Office) (801)538-5340, (Home) (801)476-8613, or R.J. Firth, Associate Director, (Home) (801)571-6068.

Page 2 Duncan Energy Company Cave Canyon Federal #3-5 Well November 5, 1992

6. Compliance with the requirements of Utah Admin. R. 649-3-20, Gas Flaring or Venting, if the well is completed for production.

Trash and sanitary waste should be properly contained and transported to approved disposal locations, not retained in or disposed of in pits on location or downhole. Prior to the commencement of drilling operations, the operator should consult the local/county sanitarian and/or the Department of Environmental Quality, Division of Drinking Water/Sanitation, regarding appropriate disposal of sanitary waste.

This approval shall expire one year after date of issuance unless substantial and continuous operation is underway or a request for an extension is made prior to the approval expiration date. The API number assigned to this well is 43-037-31696.

Sincerely,

Associate Director, Oil and Gas

ldc

**Enclosures** 

--- D....

Bureau of Land Management

J.L. Thompson

WOI1

# DIVISION OF OIL, GAS AND MINING

# SPUDDING INFORMATION

NAME OF COMPANY: DUNCAN ENERGY	43-037-31696
WELL NAME: CAVE CANYON FEDERAL	3-5
Section 3 Township 38S	Range 24E County SAN JUAN
Drilling Contractor ARAPHOE	
Rig #4	
SPUDDED: Date 11/6/92	
Time	CONICIDENTIAL
How_ROTARY	CONFIDENTIAL
Drilling will commence	
Reported by GLENN GOODWIN-DOGM	
Telephone #	<del></del>

Date 12/2/92 SIGNED JLT

Form 3160-5 (June 1990)

# UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

5. Lease Designation and Serial No.

Do not use this form for proposals to dr Use "APPLICATION FO  SUBMIT  1. Type of Well	AND REPORTS ON WELLS ill or to deepen or reentry to a different reservoir. R PERMIT—" for such proposals  IN TRIPLICATE	U-47876  6. If Indian, Allottee or Tribe Name N/A  7. If Unit or CA, Agreement Designation Cave Canyon Lease Water
Oil Gas Uther	DEC 1 4 1992	8. Well Name and No.
2. Name of Operator		Cave Canyon 3-5
Duncan Energy Company	——————————————————————————————————————	9. API Well No.
3. Address and Telephone No.		43-037-31696
1777 S. Harrison St. P-1 De	enver, CO 303-759-3303 GAS & MINING	10. Field and Pool, or Exploratory Area
4. Location of Well (Footage, Sec., T., R., M., or Survey D	escription)	Cave Canyon Field
2150' FSL & 2550' FEL NWSE	T20CD2/F	11. County or Parish, State
	\$c3	San Juan, UT
12. CHECK APPROPRIATE BOX	(s) TO INDICATE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION	TYPE OF ACTION	
Notice of Intent	Abandonment	Change of Plans
_	Recompletion	New Construction
Subsequent Report	Plugging Back	Non-Routine Fracturing
<u></u>	Casing Repair	Water Shut-Off
Final Abandonment Notice	Altering Casing	Conversion to Injection
Notification of Spud	Other	Dispose Water (Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)
	all pertinent details, and give pertinent dates, including estimated date of starting ical depths for all markers and zones pertinent to this work.)*	any proposed work. If well is directionally drilled,

Duncan Energy Company spud subject well 12-8-92 with Arapahoe Drlg rig #4.

14. I hereby certify that the foreaging is true and correct Signed Aure Clefe	Sr. Engineering Technician		_
(This space for Federal or State office use)  Approved by Conditions of approval, if any:	Title	Date	

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Form 3160-5 (June 1990)

# UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

BUREAU OF I	LAND MANAGEMENT	5. Lease Designation and Serial No.
		U-47876
SUNDRY NOTICES	AND REPORTS ON WELLS	6. If Indian, Allottee or Tribe Name
Do not use this form for proposals to dr	ill or to deepen or reentry to a different reservoi	r. N/A
Use "APPLICATION FO	R PERMIT—" for suct programment	NA
	IN INCOME.	7. If Unit or CA, Agreement Designation
SUBMIT	IN TRIPLICATE	
1. Type of Well	JAN 1 1 1993	Cave Canyon Lease Wtrflo
Oil Gas Well X Other Dry	1773	8. Well Name and No.
2. Name of Operator	Oll/Iclov	Cave Canyon 3-5
Duncan Energy Company	DIVISION OF	9. API Well No.
3. Address and Telephone No.	O'L GAS & MINING	43-037-31696
1777 S. Harrison St. P-1	303-759-3303	10. Field and Pool, or Exploratory Area
4. Location of Well (Footage, Sec., T., R., M., or Survey D		Corre Common Ed - 1 d
	·	Cave Canyon Field  11. County or Parish, State
2150' FSL & 2550' FEL 3-T38	R24E NWSE	
	RZ-L IWOL	San Juan, UT
CHECK ADDRODDIATE DOV	A TO INDICATE NATURE OF NOTICE REP	ODT OD OTHER DATA
12. CHECK APPROPRIATE BOX(	s) TO INDICATE NATURE OF NOTICE, REP	ORI, OR OTHER DATA
TYPE OF SUBMISSION	TYPE OF ACTION	ON .
	<u> </u>	
☐ Notice of Intent	X   Abandonment	Change of Plans
Subsequent Report	Recompletion	New Construction
Subsequent Report	Plugging Back	Non-Routine Fracturing
Final Abandonment Notice	Casing Repair	Water Shut-Off
LI Final Abandonment Notice	Altering Casing	Conversion to Injection
	Other	Dispose Water (Note: Report results of multiple completion on Well
	Il pertinent details, and give pertinent dates, including estimated date of sta	Completion or Recompletion Report and Log form.)
Duncan Energy Company p	lugged the subject well 12-23-92.  Moab, UT Bureau of Land Management,  Log Tops: Ismay Mass. Anhydr: Hovenweep Shallower Ismay Gothic Desert Crk	on 12-23-92.  5631 ite 5681
Location will be restor once the work is comple  14. I hereby certify that the foregoing is true and correct Signed Marie Office use).	ed per BLM requirements. A sundry te.  Title Sr. Engineering Technician	
Approved by	Title	Date
		Date

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Form 3160-4 (November 1983) (fcinerly 9-330)

# UNITED STATES

SUBMIT IN DUPLICAT

Form approved. JUN 7 - 1991 Budget Bureau No. 1004-0137 Expires August 31, 1985

# DEPARTMENT OF THE INTERIOR

(See other in

structions on reverse side) 5. LEASE DESIGNATION AND SERIAL! NO. BUREAU OF LAND MANAGEMENT <u>U-47876</u> WELL COMPLETION OR RECOMPLETION REPORT AND LOG* 6. IF INDIAN, ALLOTTEE OR TRIBE NAME 150 1a. TYPE OF WELL: DRY X Other UNIT AGREEMENT NAME b. TYPE OF COMPLETION: WELL . WORK Cave Canyon Lease Wtrflood PLUG BACK DIFF. RESVR. P&A S. FARM OR LEASE NAME 2. NAME OF OPERATOR Cave Canyon Duncan Energy Company WELL NO. 3. ADDRESS OF OPERATOR 3-5 1777 S. Harrison St. P-1 Denver, CO 80210 JAN-10. FIELD AND POOL, OR WILDCAT 4. LOCATION OF WELL (Report location clearly and in accordance with any State requirem At surface 2150 FSL & 2550 FEL NWSE Cave Canyon Field 3-T38N-R24E 11. SEC., T., R., M., OR BLOCK AND SURVEY DIVISION OF Same OR AREA At top prod. interval reported below OIL GAS & MINING 3-T38**X**-R24E At total depth Same 14. PERMIT NO. DATE ISSUED 12. COUNTY OR 13. STATE Saharjuan 43-037-31696 11-5-92 IIT 15. DATE SPUDDED 16. DATE T.D. REACHED 17. DATE COMPL. (Ready to prod.) 18. ELEVATIONS (DF, RKB, RT, GR, ETC.) • 5220 GL, 5233 KB 19. ELEV. CASINGHEAD 12-8-92 12-23-92 N/A 20. TOTAL DEPTH, MD & TVD 21. PLUG, BACK T.D., MD & TVD 23. INTERVALS DRILLED BY 22. IF MULTIPLE COMPL., ROTARY TOOLS CABLE TOOLS HOW MANY 5944 N/A X 24. PRODUCING INTERVAL(S), OF THIS COMPLETION-TOP, BOTTOM, NAME (MD AND TVD)* 25. WAS DIRECTIONAL N/A SURVEY MADE 54 5.0 (1.1.8) NO 26. TYPE ELECTRIC AND OTHER LOGS RUN LYBERLOOK WAS WELL CORED Neutron Density, DIL, SFL NO. BORZHOLE 7 7 COMP SONIC 1-12-93 23. CASING RECORD (Report all strings set in well) CARING SIZE WEIGHT, LB./FT. HOLE SIZE DEPTH SET (MD) CEMENTING RECORD AMOUNT PHILLED 13 3/8 61# 116 17 1/2" 450 sx Lite w/add None 150 standard w/add 8.5/8" 24# 1975' <u>12 1/4"</u> 150 sx Prem B w/add None 29. LINER RECORD 30 TUBING RECORD SIZE TOP (MD) BOTTOM (MD) SACKS CEMENTS SCREEN (MD) SIZE DEPTH SET (MD) PACKER SET (MD) N/A N/A 31. PERFORATION RECORD (Interval, size and number) ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC. N/A DEPTH INTERVAL (MD) AMOUNT AND KIND OF MATERIAL USED 33 • PRODUCTION DATE FIRST PRODUCTION PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump) WELL STATUS (Producing or shut-in) N/ADATE OF TEST HOURS TESTED CHOKE SIZE PROD'N. FOR OIL-BBL. GAS-MCF. WATER-BBL. GAS-OIL BATIO TEST PERIOD FLOW. TUBING PRESS. CASING PRESSURE OIL-BBI. CALCULATED GAS-MCF WATER-RBL. 24-HOUR RATE OIL GRAVITY-API (CORR.) 34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) TEST WITNESSED BY 35. LIST OF ATTACHMENTS 36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

*(See Instructions and Spaces for Additional Data on Reverse Side)

TITLE Sr. Engineering Technician

DATE 1-5-93

1	РТН				•			The second
	TRUE VERT, DEPTH		· · · · ·			19 19 19 19 10 19 1		
TOP	MEAS, DEPTH	5631 5681	5787 5795 5857	000				
	NAME		d	Çı K				States and the
		^ HΣ	E 10 t	<b>-</b>				deli e se
DESCRIPTION, CONTENTS, ETC.								
							•	
воттом								
FORMATION TOP BOTTOM								